

UNITED STATES DEPARTMENT OF AGRICULTURE
Rural Utilities Service

BULLETIN 1753F-801(PC-5A)

SUBJECT: **RUS Standard for Service Installations at Customer
Access Locations**

TO: All Telecommunications Borrowers
RUS Telecommunications Staff

EFFECTIVE DATE: September 17, 2001

OFFICE OF PRIMARY INTEREST: Outside Plant Branch,
Telecommunications Standards Division

AVAILABILITY: This bulletin supersedes REA Bulletin 345-52, REA Standard for Service Entrance and Station Protector Installations, PC-5A, issued January 16, 1980. This bulletin can be accessed via the Internet at <http://www.usda.gov/rus/telecom/publications/bulletins.htm>

PURPOSE: This standard covers RUS service installation practices at permanent or mobile home customer access locations. This bulletin is a reformat of the text codified in 7 CFR 1755.500 through 7 CFR 1755.510 published at 66 FR 43314, dated August 17, 2001.

Every effort has been made to ensure the accuracy of this document. However, in case of discrepancies, the regulations at 7 CFR 1755.500 through 7 CFR 1755.510 are the authorized sources.

Roberta D. Purcell

Roberta D. Purcell
Assistant Administrator
Telecommunications Program

9/11/01

Date

TABLE OF CONTENTS

	CFR TO Bulletin Conversion Table	5
	Abbreviations	10
	Definitions	11
1.	Scope	17
2.	General	17
3.	Demarcation Point	19
4.	Buried Services	19
5.	Aerial Wire Services	25
6.	Aerial Cable Services	32
7.	Customer Access Location Protection	34
8.	Mobile Homes	44
9.	Construction and Assembly Unit Drawings	45
	BM50 Drawing - Buried Service Wire or Cable Installation to Pole-Mounted-Wire Terminal	46
	BM83 Drawing - Buried Service Guard	47
	312-1 Drawing - Aerial Plastic Cable Details of Wire Connections to Terminal Block	48
	501-1 Drawing - Span Clamp Attachment	49
	501-2 Drawing - Span Clamp Attachment	50
	503-2 Drawing - Service Wire Connections to Aerial Cable	51
	504 Drawing - Service Wire Attachment at Intermediate Pole	52
	505 Drawing - Aerial Service Wire Sags	53
	506 Drawing - Selection of Service Wire Attachment .	54
	507 Drawing - Insulated First Attachment for Aerial Service Wire	55
	508-1 Drawing - Uninsulated First Attachment for Aerial Service Wire	56
	510 Drawing - Insulated Intermediate Attachments for Service Wires	57
	510-1 Drawing - Uninsulated Intermediate Attachments for Service Wires	58
	510-2 Drawing - Service Entrances	59
	513 Drawing - Aerial Service Wire Run on Buildings .	60

815 Drawing - Conductor Polarity (Tip and Ring) Diagram (Aerial Plant)	61
815-1 Drawing - Buried Plant Conductor Polarity Diagram	62
958 Drawing - Buried Cable and Wire Directional Marking	63
962 Drawing - Buried Wire Service Installation on Buildings	64

TABLES AND FIGURES

Table 1 Minimum Separation for Telecommunications Wires and Cables On or In Buildings	22
Table 2 Color Codes for Tip and Ring Connections of Inside Wiring Cable	25
Table 3 Nonmetallic Reinforced Aerial Service Wire Color Code	27
Table 4 Devices for Attaching Aerial Service Wires to Buildings	30
Table 5 Grounding Conductor Size Versus Number of Circuits	37
Table 6 Typical Fastening Devices for Station Wires and Grounding Conductors	39
FIGURE 1 ANCHORING DEVICES	65
FIGURE 2 CABLE ATTACHMENT DEVICES	66
FIGURE 3 CABLE ENTRANCES AND RUNS IN BUILDINGS	67
FIGURE 4 AERIAL SERVICE WIRE CROSSING OBSTRUCTIONS WOODEN BUILDING SURFACES	68
FIGURE 5 AERIAL SERVICE WIRE CROSSING OBSTRUCTIONS MASONRY BUILDING SURFACES	69
FIGURE 6 AERIAL SERVICE WIRE CROSSING COMBUSTIBLE BUILDING PROJECTIONS	70
FIGURE 7 SUSPENSION STRAND DEADENDING ON BUILDINGS	71
FIGURE 8 GROUNDING OF TELECOMMUNICATIONS SERVICE TO ELECTRIC SERVICE (PREFERRED METHOD)	72

TABLES AND FIGURES (Continued)

FIGURE 9	ALTERNATIVE TECHNIQUE FOR BONDING TO ELECTRIC GROUND WHERE DIRECT ATTACHMENT IS NOT POSSIBLE	73
FIGURE 10	BONDING BURIED SERVICE WIRE AT STATION PROTECTOR OF NID USING SERVICE WIRE SHIELD BOND CONNECTOR ..	74
FIGURE 11	BONDING BURIED SERVICE WIRE AT FUSED STATION PROTECTOR USING SERVICE WIRE SHIELD BOND CONNECTOR	75
FIGURE 12	BONDING BURIED SERVICE WIRE AT STATION PROTECTOR OF NID USING SERVICE WIRE BONDING HARNESS	76
FIGURE 13	BONDING BURIED SERVICE WIRE AT FUSED STATION PROTECTOR USING SERVICE WIRE BONDING HARNESS	77
FIGURE 14	TERMINATION OF CONDUCTORS AND SHIELD ON STATION PROTECTOR BINDING POSTS OF NID	78
FIGURE 15	TERMINATION OF CONDUCTORS AND SHIELD ON FUSED STATION PROTECTOR BINDING POSTS	79
FIGURE 16	MULTIPAIR NID OR BET TERMINAL CONNECTIONS CONTAINING FUSELESS STATION PROTECTORS	80
FIGURE 17	NETWORK INTERFACE DEVICE (NID) INSTALLATION ELECTRIC SERVICE EQUIPMENT WITHIN 35 FEET (10.7 METERS) OF MOBILE HOME	81
FIGURE 18	NETWORK INTERFACE DEVICE (NID) INSTALLATION ELECTRIC SERVICE EQUIPMENT MORE THAN 35 FEET (10.7 METERS) FROM MOBILE HOME	82
FIGURE 19	NID TERMINATIONS	83
FIGURE 20	MOBILE HOME INSTALLATION	84

INDEX:

Outside Plant
Construction
Service Installations at Customer Access Locations
Telecommunications

CFR TO BULLETIN CONVERSION TABLE

7 CFR 1755.500 to 7 CFR 1755.510	Bulletin 1753F-801
7 CFR 1755.500	Bulletin Title
(a)	-
(b)	-
7 CFR 1755.501	Definitions
7 CFR 1755.502	1.
-	1.1
-	1.2
(b)	1.3
7 CFR 1755.503	2.
(a)	2.1
(b)	2.2
(c)	2.3
(d)	2.4
(d)(1)	2.4.1
(d)(2)	2.4.2
(e)	2.5
(f)	2.6
(g)	2.7
(h)	2.8
(i)	2.9
(j)	2.10
(k)	2.11
(l)	2.12
(m)	2.13
7 CFR 1755.504	3.
(a)	3.1
(b)	3.2
(c)	3.3
(d)	3.4
7 CFR 1755.505	4.
(a)	4.1
(b)	4.2
(c)	4.3
(d)	4.4
(e)	4.5
(e)(1)	4.5.1
(e)(2)	4.5.2
(e)(3)	4.5.3
(e)(4)	4.5.4
(e)(5)	4.5.5
(f)	4.6
(f)(1)	4.6.1
(f)(2)	4.6.2
(f)(3)	4.6.3
(f)(4)	4.6.4
(f)(5)	4.6.5
(f)(6)	4.6.6
(f)(7)	4.6.7

CFR TO BULLETIN CONVERSION TABLE

7 CFR 1755.500 to 7 CFR 1755.510	Bulletin 1753F-801
(f)(8)	4.6.8
(f)(9)	4.6.9
(f)(10)	4.6.10
(f)(11)	4.6.11
(f)(12)	4.6.12
(f)(13)	4.6.13
(g)	4.7
(h)	4.8
(h)(1)	4.8.1
(h)(2)	4.8.2
(i)	4.9
7 CFR 1755.506	5.
(a)	5.1
(b)	5.2
(c)	5.3
(d)	5.4
(e)	5.5
(f)	5.6
(g)	5.7
(h)	5.8
(i)	5.9
(j)	5.10
(k)	5.11
(l)	5.12
(m)	5.13
(n)	5.14
(o)	5.15
(o)(1)	5.15.1
(o)(2)	5.15.2
(p)	5.16
(q)	5.17
(r)	5.18
(s)	5.19
(t)	5.20
(u)	5.21
(v)	5.22
(w)	5.23
(x)	5.24
(y)	5.25
(z)	5.26
(z)(1)	5.26.1
(z)(2)	5.26.2
(z)(3)	5.26.3
(z)(3)(i)	5.26.3a
(z)(3)(ii)	5.26.3b
(aa)	5.27
(bb)	5.28
(cc)	5.29

CFR TO BULLETIN CONVERSION TABLE

7 CFR 1755.500 to 7 CFR 1755.510	Bulletin 1753F-801
(dd)	5.30
(ee)	5.31
(ff)	5.32
(gg)	5.33
(hh)	5.34
(ii)	5.35
(jj)	5.36
(kk)	5.37
(ll)	5.38
(mm)	5.39
(nn)	5.40
7 CFR 1755.507	6.
(a)	6.1
(b)	6.2
(c)	6.3
(c)(1)	6.3.1
(c)(2)	6.3.2
(c)(3)	6.3.3
(c)(4)	6.3.4
(c)(5)	6.3.5
(c)(5)(i)	6.3.5.1
(c)(5)(ii)	6.3.5.2
(c)(6)	6.3.6
(c)(7)	6.3.7
(c)(8)	6.3.8
(c)(9)	6.3.9
(c)(10)	6.3.10
(c)(11)	6.3.11
(c)(12)	6.3.12
(c)(13)	6.3.13
7 CFR 1755.508	7.
(a)	7.1
(b)	7.2
(c)	7.3
(d)	7.4
(e)	7.5
(f)	7.6
(g)	7.7
(g)(1)	7.7.1
(g)(2)	7.7.2
(g)(3)	7.7.3
(h)	7.8
(i)	7.9
(j)	7.10
(k)	7.11
(l)	7.12
(l)(1)	7.12.1
(l)(2)	7.12.2

CFR TO BULLETIN CONVERSION TABLE

7 CFR 1755.500 to 7 CFR 1755.510	Bulletin 1753F-801
(m)	7.13
(n)	7.14
(o)	7.15
(p)	7.16
(q)	7.17
(r)	7.18
(s)	7.19
(t)	7.20
(u)	7.21
(v)	7.22
(w)	7.23
(w)(1)	7.23.1
(w)(2)	7.23.2
(w)(3)	7.23.3
(w)(4)	7.23.4
(w)(5)	7.23.5
(w)(6)	7.23.6
(x)	7.24
(y)	7.25
(y)(1)	7.25.1
(y)(2)	7.25.2
(y)(3)	7.25.3
(z)	7.26
(aa)	7.27
(bb)	7.28
(bb)(1)	7.28.1
(bb)(2)	7.28.2
(bb)(3)	7.28.3
(bb)(4)	7.28.4
(bb)(5)	7.28.5
(bb)(6)	7.28.6
(bb)(7)	7.28.7
(bb)(8)	7.28.8
(cc)	7.29
(cc)(1)	7.29.1
(cc)(2)	7.29.2
(dd)	7.30
(dd)(1)	7.30.1
(dd)(2)	7.30.2
(dd)(3)	7.30.3
(dd)(4)	7.30.4
(dd)(5)	7.30.5
(ee)	7.31
(ee)(1)	7.31.1
(ee)(2)	7.31.2
(ee)(3)	7.31.3
(ee)(4)	7.31.4
(ee)(5)	7.31.5

CFR TO BULLETIN CONVERSION TABLE

7 CFR 1755.500 to 7 CFR 1755.510	Bulletin 1753F-801
(ee)(6)	7.31.6
(ee)(7)	7.31.7
(ee)(8)	7.31.8
(ff)	7.32
7 CFR 1755.509	8.
(a)	8.1
(b)	8.2
(c)	8.3
(c)(1)	8.3.1
(c)(2)	8.3.2
(d)	8.4
(e)	8.5
7 CFR 1755.510	9.
(a)	9.1
(b)	9.2
(c)	9.3

ABBREVIATIONS

ANSI	American National Standards Institute
AWG	American Wire Gauge
BET	Building Entrance Terminal
CFR	Code of Federal Regulations
cm	Centimeters
°	Degrees
DP	Demarcation Point
FCC	Federal Communications Commission
FH	Flat Head
ft or '	Feet
G	Ground
ID	Inside Diameter
IEEE	Institute of Electrical and Electronics Engineers
in. or "	Inches
kg	Kilograms
kV	Kilovolts
kg/m	Kilograms/Meter
lbs	Pounds
lb/ft	Pound/Foot
m	Meter
MDF	Main Distributing Frame
mm	Millimeters
NEC®	National Electrical Code®
NESC	National Electrical Safety Code
NFPA	National Fire Protection Association
NID	Network Interface Device
No. or #	Number
R	Ring Conductor
RH	Round Head
RUS	Rural Utilities Service
SEA	Service Entrance, Aerial
SEB	Service Entrance, Buried
T	Tip Conductor

DEFINITIONS

American National Standards Institute (ANSI): A private sector standards coordinating body which serves as the United States source and information center for all American National Standards.

Ampacity: As defined in the ANSI/National Fire Protection Association (NFPA) 70-1999, *National Electrical Code® (NEC®)*: The current in amperes that a conductor can carry continuously under the conditions of use without exceeding its temperature rating. (Reprinted with permission from NFPA 70-1999, the *National Electrical Code®*, Copyright© 1998, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.) The *National Electrical Code®* and *NEC®* are registered trademarks of the National Fire Protection Association, Inc., Quincy, MA 02269.

Bonding (Bonded): As defined in the ANSI/NFPA 70-1999, *NEC®*: The permanent joining of metallic parts to form an electrically conductive path that will ensure electrical continuity and the capacity to conduct safely any current likely to be imposed. (Reprinted with permission from NFPA 70-1999, the *National Electrical Code®*, Copyright© 1998, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.)

Bonding Harness Wire: A reliable electrical conductor purposefully connected between metal parts which are required to be electrically connected (bonded) to one another to ensure the metal parts are at similar electrical potential.

Building Entrance Terminal (BET): A BET is comprised of a housing suitable for indoor and outdoor installation which contains quick-connect or binding post terminals for terminating both telecommunications service cable conductors and inside wiring cable conductors. The BET also includes primary station protectors and a means of terminating the metallic shields of service entrance cables.

Demarcation Point (DP): As defined in the Federal Communications Commission (FCC) rules in 47 Code of Federal Regulations (CFR) part 68: The point of demarcation or interconnection between telecommunications company communications facilities and terminal equipment, protective apparatus, or wiring at a subscriber's premises. Carrier-installed facilities at, or constituting, the demarcation point shall consist of wire or a jack conforming to subpart F of 47 CFR part 68. "Premises" as used herein generally means a dwelling unit, other building or a legal unit of real property such as a lot on which a dwelling unit is located, as

determined by the telecommunications company's reasonable and nondiscriminatory standard operating practices. The "minimum point of entry" as used herein shall be either the closest practicable point to where the wiring crosses a property line or the closest practicable point to where the wiring enters a multiunit building or buildings. The telecommunications company's reasonable and nondiscriminatory standard operating practices shall determine which shall apply. The telecommunications company is not precluded from establishing reasonable clarifications of multiunit premises for determining which shall apply. Multiunit premises include, but are not limited to, residential, commercial, shopping center, and campus situations.

a. **Single Unit Installations:** For single unit installations existing as of August 13, 1990, and installations installed after that date, the DP shall be a point within 12 inches (in.) [305 millimeters (mm)] of the primary protector, where there is no protector, within 12 in. (305 mm) of where the telecommunications wire enters the customer's premises.

b. **Multiunit Installations:** (1) In multiunit premises existing as of August 13, 1990, the DP shall be determined in accordance with the local carrier's reasonable and nondiscriminatory standard operating practices. Provided, however, that where there are multiple DPs within the multiunit premises, a DP for a customer shall not be further inside the customer's premises than a point 12 in. (305 mm) from where the wiring enters the customer's premises. (2) In multiunit premises in which wiring is installed after August 13, 1990, including additions, modifications, and rearrangements of wiring existing prior to that date, the telecommunications company may establish a reasonable and nondiscriminatory practice of placing the DP at the minimum point of entry. If the telecommunications company does not elect to establish a practice of placing the DP at the minimum point of entry, the multiunit premises owner shall determine the location of the DP or DPs. The multiunit premises owner shall determine whether there shall be a single DP for all customers or separate such locations for each customer. Provided, however, that where there are multiple DPs within the multiunit premises, a DP for a customer shall not be further inside the customer's premises than a point 12 in. (305 mm) from where the wiring enters the customer's premises.

Eligible Country: Any country that applies with respect to the United States an agreement ensuring reciprocal access for United States products and services and United States suppliers to the markets of that country, as determined by the United States Trade Representative.

Fuse Link: As defined in the ANSI/NFPA 70-1999, *NEC®*: A fine gauge section of wire or cable that serves as a fuse (that is, open-circuits to interrupt the current should it become excessive) that coordinates with the telecommunications cable and wire plant, and protective devices. (Reprinted with permission from NFPA 70-1999, the *National Electrical Code®*, Copyright© 1998, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.)

Grounding Conductor: As defined in the ANSI/NFPA 70-1999, *NEC®*: A conductor used to connect equipment or the grounded circuit of a wiring system to a grounding electrode or electrodes. (Reprinted with permission from NFPA 70-1999, the *National Electrical Code®*, Copyright© 1998, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.)

Listed: As defined in the ANSI/NFPA 70-1999, *NEC®*: Equipment, materials, or services included in a list published by an organization acceptable to the authority having jurisdiction and concerned of products or services, that maintains periodic inspection of production of listed equipment or materials or periodic evaluation of services, and whose listing states that either the equipment, material, or services meets identified standards or has been tested and found suitable for a specified purpose. (Reprinted with permission from NFPA 70-1999, the *National Electrical Code®*, Copyright© 1998, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.)

Manufactured Home: As defined in the ANSI/NFPA 70-1999, *NEC®*: A factory-assembled structure or structures that bears a label identifying it as a manufactured home that is transportable in one or more sections, that is built on a permanent chassis and designed to be used as a dwelling with or without a permanent foundation where connected to the required utilities, and includes the plumbing, heating, air conditioning, and electric systems contained therein. Unless otherwise indicated, the term "mobile home" includes manufactured homes. Fine Print Note (FPN) No. 1: See the applicable building code for definition of the term permanent foundation. FPN No. 2: See 24 CFR part 3280, Manufactured Home Construction and Safety Standards, of the Federal Department of Housing and Urban Development for additional information on the definition. (Reprinted with permission from NFPA 70-1999, the *National Electrical Code®*, Copyright© 1998, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and

official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.)

Mobile Home: As defined in the ANSI/NFPA 70-1999, *NEC®*: A factory-assembled structure or structures transportable in one or more sections, that is built on a permanent chassis and designed to be used as a dwelling without a permanent foundation where connected to the required utilities, and includes the plumbing, heating, air-conditioning, and electric systems contained therein. Unless otherwise indicated, the term "mobile home" includes manufactured homes. (Reprinted with permission from NFPA 70-1999, the *National Electrical Code®*, Copyright© 1998, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.)

Motor Home: As defined in the ANSI/NFPA 70-1999, *NEC®*: A vehicular unit designed to provide temporary living quarters for recreational, camping, or travel use built on or permanently attached to a self-propelled motor vehicle chassis or on a chassis cab or van that is an integral part of the completed vehicle. (Reprinted with permission from NFPA 70-1999, the *National Electrical Code®*, Copyright© 1998, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.)

Network Interface Device (NID): A NID is comprised of a housing suitable for outdoor installation which contains a compartment accessible by only telecommunications employees which includes a primary station protector and the means for terminating telecommunications service wire conductors and metallic shields, and a compartment accessible by customers which includes an RJ-11 plug and jack of the type specified in FCC rules in 47 CFR part 68.

Primary Station Protector: An assembly which complies with RUS Bulletin 345-39, RUS Specification for Telephone Station Protectors.

Qualified Installer: A person who has extensive installation experience, complete knowledge and understanding of RUS Bulletin 1751F-805, Electrical Protection At Customer Locations; RUS Bulletin 1753F-153 (RUS Form 515d), Specifications and Drawings for Service Installations at Customer Access Locations, and applicable portions of the ANSI/NFPA 70-1999, *NEC®*, and ANSI/IEEE C2-1997, *NESC*.

Recreational Vehicle: As defined in the ANSI/NFPA 70-1999, *NEC®*: A vehicular-type unit primarily designed as temporary living quarters for recreational, camping, or travel use, which either has its own motive power or is mounted on or drawn by another vehicle. The basic entities are: travel trailer, camping trailer, truck camper, and motor home. (Reprinted with permission from NFPA 70-1999, the *National Electrical Code®*, Copyright© 1998, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.)

RUS Accepted (Material and Equipment): Equipment which RUS has reviewed and determined that:

- a. Final assembly or manufacture of the equipment is completed in the United States, its territories and possessions, or in an eligible country;
- b. The cost of components within the material or equipment manufactured in the United States, its territories and possessions, or in an eligible country is more than 50 percent of the total cost of all components used in the material or equipment; and
- c. The material or equipment is suitable for use on systems of RUS telecommunications borrowers.

RUS Technically Accepted (Material and Equipment): Equipment which RUS has reviewed and determined that the material or equipment is suitable for use on systems of RUS telecommunications borrowers but the material or equipment does not satisfy both paragraph (a) and (b) of this definition:

- a. Final assembly or manufacture of the equipment is not completed in the United States, its territories and possessions, or any eligible country; and
- b. The cost of components within the material or equipment manufactured in the United States, its territories and possessions, or in an eligible country is 50 percent or less than the total cost of all components used in the material or equipment.

Travel Trailer: As defined in the ANSI/NFPA 70-1999, *NEC®*: A vehicular unit, mounted on wheels, designed to provide temporary living quarters for recreational, camping, or travel use, of such size and weight as to not require special highway movement permits when towed by a motorized vehicle and of gross trailer area less than 320 square feet (29.7 square meters). (Reprinted with permission from NFPA 70-1999, the *National Electrical Code®*, Copyright© 1998, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.)

Truck Camper: As defined in the ANSI/NFPA 70-1999, *NEC®*: A portable unit constructed to provide temporary living quarters for recreational, travel or camping use, consisting of a roof, floor, and sides, designed to be loaded onto and unloaded from the bed of a pick-up truck. (Reprinted with permission from NFPA 70-1999, the *National Electrical Code®*, Copyright© 1998, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.)

1. SCOPE

1.1 This standard covers approved methods of making service installations at permanent or mobile home customer access locations in telecommunications systems of Rural Utilities Service (RUS) borrowers. This standard does not cover service installations at customer access locations associated with boat yards or marinas.

1.2 Service installations for customer access locations in boat yards or marinas shall be performed in accordance with Article 800, Communications Circuits, of the American National Standards Institute/National Fire Protection Association (ANSI/NFPA) 70-1999, *National Electrical Code®*(*NEC®*). The *National Electrical Code®* and *NEC®* are registered trademarks of the National Fire Protection Association, Inc., Quincy, MA 02269.

1.3 The requirements in this standard cover facilities of the type described in the Federal Communications Commissions (FCC) rules in 47 Code of Federal Regulations (CFR) part 68 for one and multi-party customer owned premises wiring.

2. GENERAL

2.1 For the purposes of this standard, a Network Interface Device (NID) shall be as defined in the definition section of this standard and shall contain both a fuseless primary station protector and a modular plug and jack for each conductor pair, up to a maximum of 11 pairs, and shall be provided by the telecommunications company and used by customers.

2.2 For the purposes of this standard, a Building Entrance Terminal (BET) shall be as defined in the definition section of this standard and shall contain both primary station protectors and connector terminals for each conductor pair, of 12 or more pairs, and shall be provided by the telecommunications company and used by customers. The primary station protectors may be either fuseless or fused.

2.3 The requirements provided in this standard have been designed to coordinate with the provisions of the ANSI/NFPA 70-1999, *National Electrical Code®* (*NEC®*), and the American National Standards Institute/Institute of Electrical and Electronics Engineers, Inc. (ANSI/IEEE) C2-1997, National Electrical Safety Code (NESC). The *National Electrical Code®* and *NEC®* are registered trademarks of the National Fire Protection Association, Inc., Quincy, MA 02269. Most state and local authorities require that utility construction comply with either the ANSI/NFPA 70-1999, *NEC®*, and ANSI/IEEE C2-1997, NESC, or some earlier editions of the ANSI/NFPA 70, *NEC®*, and ANSI/IEEE C2, NESC. Some authorities have their own more stringent codes which may or may not be embellishments of the ANSI/NFPA 70, *NEC®*, and ANSI/IEEE C2, NESC.

Bulletin 1753F-801(PC-5A)

Page 18

2.4 RUS borrowers shall make certain that all construction financed with RUS loan funds comply with:

2.4.1 The provisions of this standard and the ANSI/NFPA 70-1999, *NEC®*, and ANSI/IEEE C2-1997, NESC codes, or any more stringent local codes; or

2.4.2 The provisions of this standard with borrower added adjustments to bring construction into compliance with any more stringent local codes.

2.5 This standard is intended primarily for the installer who will perform the work. It assumes that decisions regarding the selection of grounding electrodes, locations, and types of equipment have been made by the RUS borrower or the engineer delegated by the RUS borrower.

2.6 Only a qualified installer defined in the definition section of this standard shall be assigned to make installations without advance planning and without direct supervision.

2.7 This standard contains information which is normally not provided on the construction drawings which are included in Section 9 of this standard.

2.8 All work shall be conducted in a careful and professional manner. Service wire and cable shall not be trampled on, run over by vehicles, pulled over or around abrasive objects or otherwise subjected to abuse.

2.9 When situations not covered by this standard arise, the RUS borrower or the engineer delegated by the borrower, shall specify the installation procedure to be used. The requirements of paragraph 2.10 of this section shall be complied with in every installation.

2.10 NIDs, BETs, and fused primary station protectors shall be installed and grounded to meet the requirements of the ANSI/NFPA 70-1999, *NEC®*, or local laws or ordinances, whichever are more stringent.

2.11 Battery polarity and conductor identification shall be maintained throughout the system as indicated on Construction Drawings 815 and 815-1 contained in Section 9 of this standard. Color codes and other means of conductor identification of buried and aerial service wires shall conform to the requirements of this standard.

2.12 All materials for which RUS makes acceptance determinations, such as service wires and cables, ground rods, ground rod clamps, etc., used in service entrance installations shall be RUS accepted or RUS technically accepted. Borrowers shall require contractors to obtain the borrower's approval before RUS technically accepted materials are to be used in

service entrance installations. Borrower's shall also ensure that the cost of the technically accepted materials are at least 6 percent less than the cost of equivalent RUS accepted materials, as specified in "Buy American" Requirement of the Rural Electrification Act of 1938, as amended. Materials used in service entrance installations which are of the type which RUS does not make acceptance determinations shall be of a suitable quality for their intended application as determined by the RUS borrower or the engineer delegated by the RUS borrower.

2.13 On completion of an installation, borrowers shall require the installer to make all applicable tests required by RUS Bulletin 1753F-201(PC-4), "RUS Standard for Acceptance Tests and Measurements of Telecommunications Plant."

3. DEMARCATION POINT

3.1 The demarcation point (DP) provides the physical and electrical interface between the telecommunications company's facilities and the customer's premises wiring.

3.2 The FCC rules in 47 CFR part 68 require telecommunications providers to establish a "DP" which marks a separation of the provider's facilities from the customer's (owned) premises wiring and equipment.

3.3 RUS borrowers shall observe the FCC DP requirement by installing NIDs, BETs, or fused primary station protectors when required by Section 800-30(a)(2) of the ANSI/NFPA 70-1999, *NEC®*, at all new or significantly modified customer access locations which are financed with RUS loan funds. The *National Electrical Code®* and *NEC®* are registered trademarks of the National Fire Protection Association, Inc., Quincy, MA 02269.

3.4 For all customer access locations of less than 12 pairs, RUS borrowers shall establish DPs by using either NIDs or fused primary station protectors when required by Section 800-30(a)(2) of the ANSI/NFPA 70-1999, *NEC®*. For customer access locations of 12 pairs or greater, RUS borrowers shall establish DPs using either NIDs, BETs, or fused primary station protectors when required by Section 800-30(a)(2) of the ANSI/NFPA 70-1999, *NEC®*.

4. BURIED SERVICES

4.1 Buried services of two or three pairs shall consist of Service Entrance Buried (SEB) assembly units, in accordance with RUS Bulletin 1753F-153 (RUS Form 515d), "Specifications and Drawings for Service Installations at Customer Access Locations." The wire used for buried services shall conform to the requirements of RUS Bulletin 1753F-206(PE-86), "RUS Specification for Filled Buried Wires," and shall be RUS accepted or RUS

Bulletin 1753F-801(PC-5A)

Page 20

technically accepted. The conductor size for two and three pair buried service wires shall be 22 American Wire Gauge (AWG).

4.2 Buried services of six or more pairs shall be RUS accepted or RUS technically accepted 22 AWG filled buried cable conforming to the requirements of RUS Bulletin 1753F-205(PE-39), "RUS Specification for Filled Telephone Cables."

4.3 Buried service wire or cable shall be terminated in buried plant housings using either splicing connectors or filled terminal blocks in accordance with the applicable paragraphs of RUS Bulletin 1753F-401(PC-2), "RUS Standard for Splicing Copper and Fiber Optic Cables."

4.4 Buried service wire or cable shall be identified at buried plant housings in accordance with Construction Drawing 958 contained in Section 9 of this standard.

4.5 Buried service wire or cable shall be installed up to the building in the same general manner as buried exchange cable but in addition must meet the following requirements:

4.5.1 Light weight lawn plows or trenchers shall be used;

4.5.2 The shortest feasible route commensurate with the requirements of paragraphs 7.9, 7.10, and 7.11 of Section 7 of this standard, and paragraph 4.6.1 of this section shall be followed;

4.5.3 Buried service wire or cable shall be plowed or trenched to a depth of 12 inches (in.) [305 millimeters (mm)] or greater where practicable in soil, 36 in. (914 mm) in ditches, or 3 in. (76 mm) in rock. Depths shall be measured from the top of the wire or cable to the surface of the ground or rock;

4.5.4 In the case of a layer of soil over rock either the minimum depth in rock measured to the surface of the rock, or the minimum depth in soil measured to the surface of the soil may be used; and

4.5.5 Where adequate advance planning has been done, burial of telecommunications services jointly with electric power services may be feasible. If a decision has been reached by management to provide joint occupancy services, the services may be installed using the recommendations in RUS Bulletin 1751F-640, "Design of Buried Plant - Physical Considerations."

4.6 Buried service wire or cable shall be installed on or in buildings as follows:

4.6.1 Each buried service wire or cable shall contact the building as close to the NID, BET, or fused primary station protector as practicable. Service wire or cable runs on buildings shall normally consist of a single vertical run held to the

minimum practical length. Horizontal and diagonal runs shall not be permitted;

4.6.2 Buried service wire or cable shall be located so as to avoid damage from lawn mowers, animals, gardening operations, etc.;

4.6.3 Buried service wire or cable shall be installed against a foundation wall or pillar to provide adequate support and mechanical protection;

4.6.4 Where it is likely that the service wire or cable shall be subjected to mechanical damage, the wire or cable shall be enclosed in a guard in accordance with Assembly Unit Drawing BM83 contained in Section 9 of this standard;

4.6.5 The first above-ground attachment for a buried service wire or cable, unless it is enclosed in a guard, shall not be more than 4 in. (100 mm) above final grade;

4.6.6 Uninsulated attachment devices may be used to attach buried service wire and cable to masonry and other types of noncombustible buildings and on any type of building if fuseless primary station protectors incorporated in NIDs or BETs are used and installations fully comply with Section 800-30(a)(1) of the ANSI/NFPA 70-1999, *NEC*®. The *National Electrical Code*® and *NEC*® are registered trademarks of the National Fire Protection Association, Inc., Quincy, MA 02269;

4.6.7 Insulated attachments shall be used to separate service wires or cables from woodwork where Section 800-30(a)(2) of the ANSI/NFPA 70-1999, *NEC*®, requiring the use of fused primary station protectors must be observed;

4.6.8 Minimum separation between buried service wire or cable and other facilities shall be as listed in Table 1 of this section as follows:

Table 1
Minimum Separation for Telecommunications Wires and Cables
On or In Buildings

Foreign Facility or Obstruction	Minimum Clearance In. [mm] ⁽¹⁾⁽²⁾ Telecommunications Company's Wires or Cables
Electric supply wire including neutral and grounding conductors	
Open	4 [102]
In conduit	2 [50.8]
Radio and television antennas, lead-in and grounding conductors	4 [102]
Lightning rods and lightning conductors	72 [1830] ⁽³⁾
All foreign grounding conductors except lightning rod ground conductors	2 [50.8]
Neon signs and associated wiring	6 [150]
Metallic objects - pipes (gas, cold water, oil, sewer,) and structures	2 [50.8] ⁽⁴⁾
Wires or cables of another communications system	2 [50.8]

Notes: (1) If minimum separation cannot be obtained, nonshielded wire and cable facilities shall be protected with either porcelain tubes or flexible flexible tubing as modified by Notes (3) and (4).

(2) Separation applies to crossings and parallel runs.

(3) If this separation cannot be obtained, bond the telecommunications grounding conductors or grounding electrode to the lightning rod grounding conductor or grounding electrode with at least a Number (No.) 6 AWG copper, insulated, ground wire. With this provision a minimum separation of 4 in. (100 mm) is acceptable but this provision must not be utilized if the separation cited in the table can be maintained.

(4) Increase to a minimum of 3 in. (75 mm) separation from steam or hot water pipes, heating ducts, and other heat sources.

4.6.9 Wire and cable attachments to buildings for outside mounted NIDs, BETs, or fused primary station protectors shall be in accordance with Construction Drawing 962 contained in Section 9 of this standard;

4.6.10 Appropriate devices for attaching service wire or cable on or in buildings vary with the type of building construction and the wire or cable size. Figures 1 and 2 of this standard illustrate various types of anchoring devices and their applications. The size and type of fastening device for the wire or cable size and type of surface shall be in accordance with the manufacturer's recommendation;

4.6.11 Experience indicates that there are objections from many owners of buildings covered with aluminum or vinyl siding to the drilling of holes in the siding for the attachment of wires or cables, and NIDs, BETs, or fused primary station protectors. It is, therefore, important to obtain permission from the owner before drilling holes in such siding;

4.6.12 If the NID, BET, or fused primary station protector must be mounted inside (not recommended by RUS), the service entrance into the building shall be installed in accordance with Section 800-12(c) of the ANSI/NFPA 70-1999, *NEC®*. After pulling-in the wire or cable, the free space around the cable or wire shall be carefully sealed both outside and inside with a duct sealer that has RUS acceptance or RUS technical acceptance; and

4.6.13 If the customer requests an all buried installation for an alarm system or objects to above-ground facilities because of appearance and one-party service is involved, the entrance hole shall be made below grade as shown in Sketch C of Construction Drawing 510-2 contained in Section 9 of this standard. Care shall be exercised to prevent damage to the building foundation. The hole shall be sealed as specified in paragraph 4.6.12 of this section. The installation shall comply with all the requirements of Section 800-12(c) of the ANSI/NFPA 70-1999, *NEC®*.

4.7 When the NID, BET, or fused primary station protector is to be installed inside the building, the installation shall comply with Section 800-12(c) of the ANSI/NFPA 70-1999, *NEC®*, and the outside plant wire or cable shall preferably be installed in a rigid metal or intermediate metal conduit that is grounded to an electrode in accordance with Section 800-40(b) of the ANSI/NFPA 70-1999, *NEC®*, as shown in Sketch A of Figure 3 of this standard. The shield of the outside plant wire or cable shall be bonded to the grounding terminal of the NID, BET, or fused primary station protector which in turn shall be connected to the closest, existing, and accessible grounding electrode, of the electrodes cited in Section 800-40(b) of the ANSI/NFPA 70-1999, *NEC®*.

4.8 An inside NID, BET, or fused primary station protector installation may also be made without use of a rigid metal or

intermediate metal conduit provided that the ingress of the outside plant wire or cable complies with Section 800-12(c) of the ANSI/NFPA 70-1999, *NEC®*, and provided either of the following are observed:

4.8.1 The NID, BET, or fused primary station protector is located as close as practicable to the point where the outside plant wire or cable emerges through an exterior wall. The length of outside plant wire or cable exposed within the building shall be as short as practicable but in no case shall it be longer than 50 feet (ft) [15.2 meters (m)] in accordance with the allowable exception No. 3 of Section 800-50 of the ANSI/NFPA 70-1999, *NEC®*. See Sketch B of Figure 3 of this standard. The shield of the outside plant wire or cable shall be bonded to the grounding terminal of the NID, BET, or fused primary station protector which in turn shall be connected to the closest, existing and accessible grounding electrode, of the electrodes cited in Section 800-40(b) of the ANSI/NFPA 70-1999, *NEC®* (Fine print Note No. 2 of ANSI/NFPA 70-1999, *NEC®*, Section 800-50, warns that the full 50 ft (15.2 m) may not be authorized for outside unlisted cable (not in a metal or intermediate metal conduit) within a building if it is practicable to place the NID, BET, or fused primary station protector closer than 50 ft (15.2 m) to the cable entrance point, e.g., if there is an acceptable and accessible grounding electrode of the type cited in Section 800-40(b) of the ANSI/NFPA 70-1999, *NEC®*, anywhere along the proposed routing of the outside cable within the building); or

4.8.2 Where the NID, BET, or fused primary station protector must be located within the building remote from the entrance point and the entrance point of the outside plant wire or cable cannot be designed to be closer to the NID, BET, or fused primary station protector location, the outside plant wire or cable shall be spliced, as close as practicable to the point where the outside plant wire or cable emerges through an outside wall, to an inside wiring cable that is "Listed" as being suitable for the purpose in accordance with Part E of Article 800 of the ANSI/NFPA 70-1999, *NEC®*. The length of outside plant wire or cable exposed within the building shall be as short as practicable but in no case shall it be longer than 50 ft (15.2 m) in accordance with the allowable exception No. 3 of Section 800-50 of the ANSI/NFPA 70-1999, *NEC®*. See Sketch C of Figure 3 of this standard. The shield of the outside plant wire or cable shall be bonded to the grounding terminal of the NID, BET, or fused primary station protector which in turn shall be connected to the closest, existing, and accessible grounding electrode, of the electrodes cited in Section 800-40(b) of the ANSI/NFPA 70-1999, *NEC®* (Fine print Note No. 2 of the ANSI/NFPA 70-1999, *NEC®*, Section 800-50, warns that the full 50 ft (15.2 m) may not be authorized for outside unlisted cable (not in a metal or intermediate metal conduit) if it is practicable to place the NID, BET, or fused primary station protector closer than 50 ft (15.2 m) to the cable entrance point, e.g., if there is an acceptable and accessible grounding electrode of the type cited

in Section 800-40(b) of the ANSI/NFPA 70-1999, *NEC®*, anywhere along the proposed routing of the outside cable within the building).

4.9 The polarity of buried wire or cable "tip" and "ring" conductors shall be maintained by making the connections in accordance with Table 2 of this section, as follows:

Table 2
Color Codes For Tip And Ring Connections of Inside Wiring Cable

Pair	Tip		Ring	
	Color of Insulation	Color of Marking	Color of Insulation	Color of Marking
1	White	Blue	Blue	White
2	White	Orange	Orange	White
3	White	Green	Green	White
4	White	Brown	Brown	White
5	White	Slate	Slate	White
6	Red	Blue	Blue	Red
7	Red	Orange	Orange	Red
8	Red	Green	Green	Red
9	Red	Brown	Brown	Red
10	Red	Slate	Slate	Red
11	Black	Blue	Blue	Black
12	Black	Orange	Orange	Black
13	Black	Green	Green	Black
14	Black	Brown	Brown	Black
15	Black	Slate	Slate	Black
16	Yellow	Blue	Blue	Yellow
17	Yellow	Orange	Orange	Yellow
18	Yellow	Green	Green	Yellow
19	Yellow	Brown	Brown	Yellow
20	Yellow	Slate	Slate	Yellow
21	Violet	Blue	Blue	Violet
22	Violet	Orange	Orange	Violet
23	Violet	Green	Green	Violet
24	Violet	Brown	Brown	Violet
25	Violet	Slate	Slate	Violet

5. AERIAL WIRE SERVICES

5.1 Aerial services of one through six pairs shall consist of Service Entrance Aerial (SEA) assembly units, in accordance with RUS Bulletin 1753F-153 (RUS Form 515d), "Specifications and Drawings for Service Installations at Customer Access Locations. The wire used for aerial services shall conform to the requirements of RUS Bulletin 1753F-204(PE-7), "RUS Specification for Aerial Service Wires," and shall be RUS accepted or RUS technically accepted.

5.2 If aerial wire services are to be connected to aerial cable pairs, the NIDs or fused primary station protectors and grounds shall be installed and connected before the aerial service wires are attached to the customer's structure.

5.3 Kinks or splices shall not be permitted in aerial service wire spans.

5.4 Aerial service wires shall be run in accordance with the Construction Drawings contained in Section 9 of this standard and shall conform to all clearance requirements of the ANSI/NFPA 70-1999, *NEC*®, and ANSI/IEEE C2-1997, NESC, or local laws or ordinances, whichever are the most stringent. The *National Electrical Code*® and *NEC*® are registered trademarks of the National Fire Protection Association, Inc., Quincy, MA 02269.

5.5 Aerial service wire shall be installed using the maximum practicable sag consistent with the required ground clearance and good construction practices. In no event shall the minimum sags be less than the values shown on Construction Drawing 505 contained in Section 9 of this standard for various span lengths and loading areas provided. Span lengths shall not exceed 250 ft (76 m).

5.6 To reduce vibration and galloping, aerial service wire shall be twisted one complete turn for each 10 ft (3 m) of span length at the time of installation.

5.7 The methods of attaching aerial service wires at poles shall be as illustrated in Construction Drawings 503-2 and 504 contained in Section 9 of this standard.

5.8 Horizontal and vertical climbing spaces on poles used jointly with power circuits shall be provided in conformance with the requirements of Rule 236 of ANSI/IEEE C2-1997, NESC.

5.9 Not more than four aerial service wires shall be distributed from any one 7/16 in. (10 mm) drive hook, or more than two aerial service wires from any one 5/16 in. (8 mm) drive hook. Aerial service wires and drive hooks shall be arranged so that the load does not pull the drive hook out of the pole. When more than one drive hook is required, the drive hooks shall be staggered with a minimum separation of 1 in. (25.4 mm) horizontally on centers and 1.5 in. (40 mm) vertically on centers. If drive hooks are placed within 3 in. (76 mm) of the top of the pole and on the opposite side of the pole's circumference, a vertical separation of at least 3 in. (76 mm) shall be provided. A drive hook shall not be placed on the top of a pole or stub pole.

5.10 When connecting aerial service wires to cable pairs at terminals, sufficient slack shall be provided so that each aerial service wire shall reach any binding post position as shown on Construction Drawing 312-1 contained in Section 9 of this standard.

5.11 Aerial service wire attachments on utility poles and the manner of placing bridle rings and entering cable terminals shall be as shown on Construction Drawing 503-2 contained in Section 9 of this standard.

5.12 Not more than two conductors shall be connected to any terminal binding post. Where it is necessary to bridge more than two aerial service wires at the same closure, the aerial service wires shall be terminated in aerial service wire terminals connected in parallel with a No. 20 AWG bridle wire which shall be terminated on the binding posts of the filled terminal block.

5.13 Where aerial service wire is attached to aerial plastic cable, it shall be brought directly into a ready-access closure and shall be terminated on the binding posts of the filled terminal block as shown on Construction Drawing 503-2 contained in Section 9 of this standard.

5.14 The conductor of copper coated steel reinforced aerial service wires identified by tracer ridges shall be used as the ring (negative battery) conductor of the pair, and shall normally be connected to the right or lower binding post of a pair on filled terminal blocks and NIDs or fused primary station protectors.

5.15 Nonmetallic Reinforced Aerial Service Wire Pair Identification.

5.15.1 The tip and ring conductors of nonmetallic reinforced aerial service wires shall be identified in accordance with Table 3 of this section, as follows:

Table 3
Nonmetallic Reinforced Aerial Service Wire Color Code

Pair Number	Conductor Color	
	Tip	Ring
1	White/Blue or White	Blue
2	White/Orange or White	Orange
3	White/Green or White	Green
4	White/Brown or White	Brown
5	White/Slate or White	Slate
6	Red/Blue or Red	Blue

5.15.2 The ring (negative battery) conductor of the pair shall normally be connected to the right or lower binding post of a pair on filled terminal blocks and NIDs or fused primary station protectors.

5.16 When it is necessary to avoid intervening obstacles between a pole and a building, span clamp attachments shall be used to support the aerial service wires at points between the poles that

are supporting the cable on the suspension strand as indicated by Construction Drawings 501-1 and 501-2 contained in Section 9 of this standard.

5.17 Aerial service wire strung from pole to pole shall be placed entirely below or entirely above any existing wire or cable. When adequate ground clearance can be obtained, preference shall be given to placing aerial service wire below wire and cable.

5.18 When more than one aerial service wire is installed from pole to pole, the first aerial service wire shall be sagged in accordance with Construction Drawing 505 contained in Section 9 of this standard. Succeeding aerial service wires shall be sagged with 2 in. (50.8 mm) more sag for each aerial service wire.

5.19 Aerial service wire spans from pole lines to buildings shall follow the shortest feasible route commensurate with the requirements of paragraph 5.20 of this section and shall be sagged in accordance with Construction Drawing 505 contained in Section 9 of this standard. The route shall avoid trees and other obstructions to the extent practicable. Where trees cannot be avoided, tree trimming permission shall be obtained from the owner or the owner's representative, and all limbs and foliage within 2 ft (600 mm) of the finally sagged wire shall be removed. If tree trimming permission cannot be obtained, the matter shall be referred to the borrower for resolution before proceeding with the installation.

5.20 Aerial service wires shall contact buildings as closely as practicable at a point directly above the NID, or fused primary station protector. Generally, horizontal drop wire runs on buildings shall not exceed 20 ft (6 m). The warning given in paragraph 4.6.11 of Section 4 of this standard regarding drilling holes in aluminum and vinyl siding applies also to attaching aerial service wires.

5.21 The point of the first building attachment shall be located so that the aerial service wire will be clear of roof drainage points.

5.22 Where practicable, aerial service wires shall pass under electrical guys, power distribution secondaries and services, tree limbs, etc.

5.23 Aerial service wire shall not pass in front of windows or immediately above doors.

5.24 Aerial service wires shall be routed so as to have a minimum clearance of 2 ft (600 mm) from any part of a short wave, ham radio, etc. antenna mast and a television antenna mast in its normal vertical position and of the possible region through which it sweeps when being lowered to a horizontal position.

5.25 Aerial service wires shall be installed such that all clearances and separations comply with either Section 237 of the ANSI/IEEE C2-1997, NESC, or ANSI/NFPA 70-1999, *NEC®*, or local laws or ordinances, whichever is the most stringent.

5.26 Aerial service wire attachments to buildings shall be as follows:

5.26.1 First attachments on buildings shall be made in accordance with Construction Drawings 506, 507, or 508-1 contained in Section 9 of this standard, as applicable;

5.26.2 Intermediate attachments on buildings shall be made in accordance with Construction Drawings 510 or 510-1 contained in Section 9 of this standard; and

5.26.3 Uninsulated attachments shall be permitted to be used as follows:

- a. Wherever NIDs are used as permitted by Section 800-30(a)(1) of the ANSI/NFPA 70-1999, *NEC®*; and
- b. On masonry and other types of nonflammable buildings.

5.27 Insulated attachments shall be used on wooden frame, metallic siding and other types of combustible buildings where fused primary station protectors are used, as required by Section 800-30(a)(2) of the ANSI/NFPA 70-1999, *NEC®*.

5.28 Aerial service wire runs on buildings shall be attached vertically and horizontally in a neat and most inconspicuous possible manner. See Construction Drawing 513 contained in Section 9 of this standard. Horizontal runs on buildings are undesirable and shall be kept to a minimum. Diagonal runs shall not be made.

5.29 Aerial service wire runs on buildings shall be located so as not to be subjected to damage from passing vehicles, pedestrians, or livestock.

5.30 Minimum separation between aerial service wires and other facilities on or in buildings shall be in accordance with Table 1 in paragraph 4.6.8 of Section 4 of this standard.

5.31 Appropriate devices for attaching aerial service wires to buildings vary with the type of building construction and with the type of customer access location equipment. Table 4 of this section lists various types of attachments and their application with respect to construction, customer access location equipment, and proper mounting devices. Construction Drawings 506 through 513 contained in Section 9 of this standard illustrate requirements with respect to various angles of service wire contacts and uses of various attachments. Table 4 of this section is as follows:

Table 4
DEVICES FOR ATTACHING AERIAL SERVICE WIRES TO BUILDINGS (1), (2), (8)

TYPE OF ATTACHMENT		TYPES OF FASTENING DEVICES											
		FRAME BUILDINGS (3)								FIRE RESISTANT BUILDINGS (4)			
		FUSED STATION PROTECTOR				NID				(NID OR FUSED STATION PROTECTOR)			
		Wood Shingle—Composition (5)	Plywood—Plastic—Board Paneling	Thin Brick—Stucco—Plaster	Metal Sheath	Wood Shingle—Composition (5)	Plywood—Plastic—Board Paneling	Thin Brick—Stucco—Plaster	Metal Sheath	Concrete Block	Tile	Brick Stone Concrete	Steel
Knob, S	Under 30° Angle	2-1/2" x #18 FH Screw	3" x #18 FH Screw	3" x #18 FH Screw	2-1/2" x #18 FH Screw	2-1/2" x #18 FH Screw	3" x #18 FH Screw	3" x #18 FH Screw	2-1/2" x #18 FH Screw				
	Over 30° Angle	5/16" Angle Screw	5/16" Angle Screw	3/8" Angle Screw	5/16" Angle Screw	5/16" Angle Screw	5/16" Angle Screw	3/8" Angle Screw	5/16" Angle Screw				
Knob, C		2-1/2" x #10 RH Screw	3" x #10 RH Screw	3-1/2" x #10 RH Screw	2-1/2" x #10 RH Screw	Note 6	Note 6	Note 6	Note 6				
Bracket, House		2" x #14 RH Screw	2" x #14 RH Screw	2-1/2" x #14 RH Screw	2" x #14 RH Screw	Note 6	Note 6	Note 6	Note 6				
Bracket, Corner		2" x #14 RH Screw	2" x #14 RH Screw	2-1/2" x #14 RH Screw	2" x #14 RH Screw	2" x #14 RH Screw	2" x #14 RH Screw	2-1/2" x #14 RH Screw	2" x #14 RH Screw	3/16" x 4" Toggle	3/16" x 4" Toggle	2" x #14 RH Screw	3/16" x 4" Toggle
Screweye, Insulated		1" Shank	1" Shank	2" Shank	1" Shank	Note 6	Note 6	Note 6	Note 6				
Ring, Bridle, Drive		Note 6	Note 6	Note 6	Note 6	Note 7	Note 7	Note 6	Note 7	Drive Anchor	Note 6	Drive Anchor	Note 6
Ring, Bridle, Screw		Note 6	Note 6	Note 6	Note 6	Note 7	Note 7	Note 6	Note 7	Expansion Anchor	Note 6	Expansion Anchor	Note 6
Hook, Drop Wire		Note 6	Note 6	Note 6	Note 6	2" x #14 RH Screw	2" x #14 RH Screw	2" x #14 RH Screw	2" x #14 RH Screw	1/4" x 4" Toggle	1/4" x 4" Toggle	2" x #18 RH Screw	1/4" x 3" Toggle
Hook, House		Note 6	Note 6	Note 6	Note 6	2" x #14 RH Screw	2" x #14 RH Screw	2" x #14 RH Screw	2" x #14 RH Screw	Expansion Anchor	Note 6	Expansion Anchor	Note 6
Ring, Bridle, Toggle										3/16" x 4" Toggle	3/16" x 4" Toggle	Note 6	3/16" x 4" Toggle
Clamp, One Hole, Offset or closed "U" Cable Strap		Note 6	Note 6	Note 6	Note 6	3/4" x #6 RH Screw	3/4" x #6 RH Screw	3/4" x #6 RH Screw	3/4" x #6 RH Screw	1" x #6 RH Screw	1/8" x 4" Toggle	1" x #6 RH Screw	1/2" x #6 SM Screw

- Notes:** (1) Screw dimensions are minimum. Where appropriate, either or both dimensions shall be increased. All wood screws for exterior use shall be stainless steel. All other exterior metal devices shall be stainless steel, zinc coated steel, silicon bronze, or corrosion resistant aluminum alloy.
- (2) Toggle bolt dimensions are minimum. Where appropriate, either or both dimensions shall be increased.
- (3) All devices should be attached to studding.
- (4) Screw-type devices shall be secured by means of expansion-type anchors. Equivalent manual or machine-driven devices may be used. Where toggle bolts are specified equivalent devices may be used.
- (5) Pilot holes shall be provided for screws and bridle rings in shingles and dropsiding.
- (6) Attachment device not applicable.
- (7) Attachment device applicable but no separate fastening device required.
- (8) To convert English units to Metric units use
1 in. = 25.4 mm.

5.32 Fastener spacings for vertical and horizontal runs on frame or masonry buildings shall not be more than 6 ft (2 m) apart. Fasteners should be spaced close enough to prevent the aerial service wire from "slapping" against the building during windy conditions.

5.33 When it is necessary to pass behind or around obstructions such as downspouts and vertical conduits, the aerial service wire shall be supported firmly with attachment devices placed not more than 6 in. (152 mm) from the obstruction as illustrated in Figures 4 and 5 of this standard. Preferably, the aerial service wire should be routed behind obstructions to minimize the possibility of mechanical damage to the aerial service wire in the event repair work to the obstruction is required.

5.34 When passing around building projections of masonry or wood or around corners, aerial service wires shall be installed as illustrated in Figures 5 and 6 of this standard.

5.35 In areas where ice and snow conditions are severe, aerial service wires shall be located so that ice and snow falling from the roof will not strike the wires. However, where aerial service wires must pass under the sloping part of the roof, first attachments shall be made as close as practicable to the eaves.

5.36 If two aerial service wire spans are required to the same building, the first attachment shall be such that both aerial service wires can be attached at the same attachment device. Refer to Construction Drawing 508-1 contained in Section 9 of this standard. Where more than two aerial service wires are required, additional attachment devices in the same general location on the building shall be used.

5.37 When two or more aerial service wire runs are required on the same building they shall share the same type of attachment devices.

5.38 Aerial service wire entrances to buildings shall conform to Sketch B of Construction Drawing 510-2 contained in Section 9 of this standard, unless the entrance is made through a conduit.

5.39 When the aerial service wire approaches the entrance hole from above, a 1.5 in. (40 mm) minimum drip loop shall be formed in accordance with Sketch B of Construction Drawing 510-2 contained in Section 9 of this standard.

5.40 If an entrance conduit which slopes upward from outside to inside is available and suitably located, it shall be used for the aerial service wire entrance.

6. AERIAL CABLE SERVICES

6.1 Where more than six pairs are needed initially, and where an aerial service is necessary, the service shall consist of 22 AWG filled aerial cable of a pair size adequate for the ultimate anticipated service needs of the building. The cable shall comply with the requirements of RUS Bulletin 1753F-205(PE-39), "RUS Specification for Filled Telephone Cables," and shall be RUS accepted or technically accepted.

6.2 Aerial cable services shall be constructed in accordance with specific installation specifications prepared by the RUS borrower or the engineer delegated by the borrower.

6.3 Unless otherwise specified in the installation specifications, aerial cable service installations shall meet the following requirements:

6.3.1 Strand supported lashed construction shall be used;

6.3.2 Where practicable a 5/16 in. (8 mm) utility grade strand and automatic clamps shall be used in slack spans to avoid damage to the building;

6.3.3 Construction on poles shall comply with applicable construction drawings for regular line construction. Aerial service cable shall be spliced to the main cable in accordance

with RUS Bulletin 1753F-401(PC-2), "RUS Standard for Splicing Copper and Fiber Optic Cables";

6.3.4 Where practicable, aerial cable shall pass under electrical guys, distribution secondaries, and services;

6.3.5 The suspension strand shall be attached to the building by wall brackets as indicated in Figure 7 of this standard.

6.3.5.1 If taut spans are necessary, appropriate size strand may be used if the pull is in line with one wall of the building, or within 20 degrees of being in line as illustrated in Sketch A of Figure 7 of this standard. If the angle of pull is greater than 20 degrees from the building, the wall bracket shall be reinforced against pullout by an arrangement equivalent to Sketch B of Figure 7 of this standard. Taut spans may be strung using the recommendations in RUS Bulletin 1751F-630, "Design of Aerial Plant." The same tension as would be used in normal line construction so as not to exceed 60 percent of the breaking strength of the strand under maximum loading shall be used. Taut spans shall not exceed 100 ft (30.5 m) in length and the cable weight shall not exceed 1 pound/foot (lb/ft) [1.5 kilogram/meter (kg/m)] except when equivalent combinations of greater span lengths with cable weight less than 1 lb/ft (1.5 kg/m) are permissible.

6.3.5.2 When an attachment must be made to the face of a building wall away from a corner, a "U" type wall bracket shall be used as indicated in Sketch C of Figure 7 of this standard. Only slack span construction with 5/16 in. (8 mm) utility grade strand shall be permitted in this situation. The bail of the automatic clamp shall be protected by a wire rope thimble.

6.3.6 Aerial cable shall be located on the rear or side of the building and shall be run only in a horizontal or a vertical direction. The cable route shall be selected so as to avoid building projections and obstructions to the extent practicable;

6.3.7 Cable attachment devices shall be located in solid masonry or on studs of wood frame buildings. Cable attachment devices may be installed on sheet surface materials only when such materials are reinforced with a backing material which allows penetration and firm holding of the attachment devices through the backing material;

6.3.8 The minimum separation on or in buildings between cable and other facilities shall be as indicated in Table 1 of paragraph 4.6.8 of Section 4 of this standard;

6.3.9 On horizontal runs, cable clamps shall be placed so that the attachment is below the cable. On vertical runs, cable clamps shall be placed so that the attachment is on the same side as horizontal runs. Cable clamps shall be placed on the inside of cable bends;

6.3.10 On horizontal runs, cable clamps shall be placed not more than 16 in. (400 mm) apart for cable diameters equal to or greater than 1 in. (25.4 mm) and 24 in. (600 mm) apart for cable diameters less than 1 in. (25.4 mm);

6.3.11 On vertical runs, cable clamps shall be approximately 24 in. (600 mm) apart for all sizes of cable;

6.3.12 For the cable entrance, holes shall be bored slightly larger in diameter than the cable and shall slope upward from outside to inside. A duct sealer having RUS acceptance or RUS technical acceptance shall be applied to both ends of the hole after the cable is pulled in; and

6.3.13 Paragraphs 4.7 and 4.8 of Section 4 of this standard shall also apply to aerial cable services.

7. CUSTOMER ACCESS LOCATION PROTECTION

7.1 All customer access locations shall be protected.

7.2 Customer access location protection shall consist of installing the telecommunications facilities with proper clearances and insulation from other facilities, providing primary voltage limiting protection, fuse links, NIDs, BETs, or fused primary station protectors, if required, and adequate bonding and grounding.

7.3 All NIDs shall be RUS accepted or RUS technically accepted or the RUS borrower shall obtain RUS regional office approval on a case by case basis as applicable.

7.4 All BETs shall be RUS accepted or RUS technically accepted.

7.5 All fused primary station protectors shall be RUS accepted or RUS technically accepted.

7.6 NIDs, BETs, or fused primary station protectors shall be mounted outside for all applications except for those described in paragraphs 7.7 through 7.7.3 of this section.

7.7 NIDs, BETs, or fused primary station protectors may be mounted inside when:

7.7.1 Large buildings are to be served and the customer requests an inside installation;

7.7.2 Buried alarm circuits are requested by the subscriber; or

7.7.3 The customer requests an all buried installation for appearance or to prevent the drilling of holes in aluminum or vinyl siding.

7.8 Outside mounted NIDs, BETs, or fused primary station protectors shall be easily accessible and shall be located between 3 to 5 ft (1 to 1.5 m) above final grade.

7.9 The locations of NIDs, BETs, or fused primary station protectors shall be selected with emphasis on utilizing the shortest primary station protector grounding conductor practicable and on grounding of the telecommunications primary station protector to the electric service grounding system established at the building served utilizing electrodes (c) through (g) cited in Section 800-40(b)(1) of the ANSI/NFPA 70-1999, *NEC®*. The *National Electrical Code®* and *NEC®* are registered trademarks of the National Fire Protection Association, Inc., Quincy, MA 02269.

7.10 If access to the building electric service grounding system, as referenced in paragraph 7.9 of this section, is not possible or is not reasonable [telecommunications primary station protector grounding conductor will be longer than 10 ft (3 m)], the NID, BET, or fused primary station protector shall be located as close as practicable to electrodes (a) or (b) cited in Section 800-40(b)(1) of the ANSI/NFPA 70-1999, *NEC®*.

7.11 In addition, the NID, BET, or fused primary station protector shall be located in, on, or immediately adjacent to the structure or building to be served as close as practicable to the point at which the telecommunications service wire attaches to the building, making sure that the telecommunications primary station protector grounding conductor is connected to the closest, existing, and accessible electrode, of the electrodes cited in paragraph 7.9 or 7.10 of this section.

7.12 For the preferred customer access location installation, the ANSI/NFPA 70-1999, *NEC®*, permits the telecommunications grounding conductor to be connected to the metallic conduit, service equipment closure, or electric grounding conductor as shown in Figure 8 of this standard.

7.12.1 Connections to metallic conduits shall be made by ground straps clamped over a portion of the conduit that has been cleaned by sanding down to bare metal.

7.12.2 Connections to metallic service equipment closures shall be made by attaching a connector which is listed for the purpose by some organization acceptable to the local authority (State, county, etc.) per Article 100 of the ANSI/NFPA 70-1999, *NEC®*, definition for "Listed" [for example connectors listed for the purpose by Underwriters Laboratories (UL)].

7.13 Where it is not possible to accomplish the objective of paragraphs 7.9, 7.10, and 7.11 of this section, interior metallic pipes may be used to the maximum practicable extent to gain access to the electric service ground as shown in Figure 9 of this standard. Note that the water pipe in Figure 9 of this

standard is electrically continuous between electric and telecommunications bonds to the cold water pipe and it is used only as a portion of a bonding conductor and, therefore, does not have to be "acceptable" as a ground electrode but may be floating (isolated from ground by a plastic pipe section). ANSI/NFPA 70-1999, *NEC®*, requires that metal piping be used as a bonding conductor in this manner only when the connectors to the pipe are within 1.5 m (5 ft) of where the pipe enters the premises. This is not the preferred installation. The RUS preferred installation has the telecommunications primary station protector grounded directly to an accessible location near the power grounding system. See paragraphs 7.12 through 7.12.2 of this section.

7.14 Where the telecommunications premises system at a customer's access location is grounded to a separate electrode (of any type) this telecommunications grounding electrode must be bonded to the electric grounding system with a No. 6 AWG or larger copper insulated grounding conductor. Bonding of separate electrodes is a requirement of the ANSI/NFPA 70-1999, *NEC®*.

7.15 The NID, BET, or fused primary station protector pair size shall be selected for the number of lines anticipated within five years.

7.16 When lightning damage is considered probable or customer access locations are remote from the borrower's headquarters, use of maximum duty gas tube primary station protectors incorporated in NIDs, BETs, or fused primary station protectors should be considered. (See RUS TE&CM 823, "Electrical Protection by Use of Gas Tube Arresters").

7.17 NIDs or BETs incorporating fuseless station protectors shall always be used in preference to fused station protectors or BETs incorporating fused protectors, when in the judgment of the RUS borrower or the engineer delegated by the RUS borrower, the requirements of the ANSI/NFPA 70-1999, *NEC®*, for fuseless station protectors can be met.

7.18 A fuse link consisting of a copper conductor two gauges (AWG) finer (numerically higher) conductivity than the aerial service wire shall be provided between the cable and aerial service wire where NIDs or BETs incorporating fuseless station protectors are used. Thus for a 22 AWG drop, a fuse link of No. 24 AWG or finer copper wire shall be provided. If the cable circuit is No. 24 gauge or finer, the cable conductors serve as the fuse link for the 22 AWG aerial service wire and no separate fuse link is necessary. (Note: The fuse link or the facilities serving as the fuse link must be located between the telecommunications facilities that are exposed to possible power cross and the customer drop where there is no exposure to possible power cross.)

7.19 RUS's buried plant practices require buried main line plant to be protected against power contacts to aerial plant extensions and aerial inserts by No. 24 AWG fuse links at every buried-aerial junction.

7.20 In aerial cable plant, fuse links are usually provided by 24 AWG leads on filled terminal blocks regardless of the gauge of the cable conductors. This practice is acceptable if the ampacity of the aerial service wire is sufficiently higher than the fuse link's ampacity.

7.21 The grounding and bonding of each NID, BET, or fused primary station protector shall be selected by consulting paragraphs 7.9 through 7.14 of this section. The "first choice" assembly unit shall be selected whenever the prevailing conditions make its use practicable. The NID, BET, or fused primary station protector assembly unit selected shall be installed in accordance with the appropriate construction drawing specified in RUS Bulletin 1753F-153 (RUS Form 515d), "Specifications and Drawings for Service Installations at Customer Access Locations."

7.22 The minimum size grounding conductor that can be used with a single NID; a group of NIDs; a multipair NID; fused protector; or BET shall be in accordance Table 5 of this section, as follows:

Table 5
Grounding Conductor Size Versus Number of Circuits

Minimum Grounding Conductor Size	Number of Circuits	
	Fuseless (Carbon or Gas Tube)	Fused
#12 AWG, copper, insulated	1 to 2	1 to 3
#10 AWG, copper, insulated	3 to 5	4 to 7
#6 AWG, copper, insulated	6 or more	8 or more

7.23 Grounding conductor runs between the NID, BET, or fused station protector and the ground electrode shall conform to the following:

7.23.1 The shortest, most direct route practicable shall be used;

7.23.2 Sharp bends in the grounding conductor shall be avoided during installation;

7.23.3 No splices shall be made in the grounding conductor;

7.23.4 Grounding conductors shall not be fished through walls, under floors, or placed in bridle rings or any metal conduit unless the grounding conductor is bonded to the conductor at both ends of the metallic conduit;

7.23.5 Grounding conductor runs from an outside mounted NID, BET, or fused station protector to an inside ground electrode shall use the same entrance as the station wire; and

7.23.6 Grounding conductor runs from an outside mounted NID, BET, or fused station protector to an outside ground electrode at the building shall be attached to the exterior surface of the building or buried. If buried, the grounding conductor shall be either plowed or trenched to a minimum depth of 12 in. (300 mm). When trenched, the trenches shall be as close to the side of the building as practicable, backfilled, and tamped to restore the earth to its original condition.

7.24 Telecommunications grounding connectors shall be RUS accepted or technically accepted. Grounding and bonding conductors shall be made of copper. Where the grounding and bonding conductors must be connected to aluminum electric service grounding conductors, bimetal grounding connectors shall be used.

7.25 Grounding conductor attachments shall conform to the following:

7.25.1 Galvanized nails or clamps, or nickel-copper alloy staples shall be used for grounding conductor attachments in accordance with Table 6 of this section;

7.25.2 Grounding conductors, station or buried service wires in parallel runs may share the same fastening device when the device is specifically designed for two wires. See Table 6 of this section for station wire and grounding conductor fasteners; and

7.25.3 Grounding conductor fasteners shall be placed 12 to 18 in. (300 to 450 mm) apart on straight runs and 2 to 4 in. (50.8 to 100 mm) apart at corners and at bends. Table 6 of this section is as follows:

Table 6

TYPICAL FASTENING DEVICES FOR STATION WIRES AND GROUNDING CONDUCTORS (9)

TYPE AND GAUGE OF WIRE		APPROX. OVERALL DIAMETER	TYPES OF FASTENING DEVICES FOR VARIOUS TYPES OF BUILDINGS OR WALL FINISHES																				
			Hard Woods	Soft Woods	Wallboard, Plaster on Wood, or Metal Lath, or Concrete Block(3)	Brick, Stone or Concrete(3)	Shingles and Siding(4)	Sheet Metal(5)	Wall Tile(3)														
#22 AWG Station Wire		.125 in. to .155 in.	A1, D7, E1, F1, G1	A2, A3, D8, E2, F2, G2	D8, D9, E2, E3, G2, G3	D8, E2, G2	A2, A3, D7, D8, E2, F2	D7, D8, D9, G1, G2, G3, H1	D8, D9, E2, E3, G2, G3, H1														
GROUNDING CONDUCTOR	#10 AWG Insulated Wire	.168 in.	A1, B1, D1	A2, A3, B1, B2, D2	B2, D2, D3	B2, D2	A2, A3, B1, B2, D1, D2	D1, D2, D3, H2	B2, D2, D3, H2														
	#12 AWG Insulated Wire	.127 in.	A1, B1, C1, E1, F1, D7, G1	A2, B1, B2, C1, C2, D8, E2, F2, G2	B2, C2, C3, D8, D9, E2, E3, G2, G3	B1, B2, C2, D8, E2, E3, G2	A2, A3, B1, B2, C1, C2, D8, E2, F2, G2	C1, C2, C3, D7, D8, D9, E1, E2, E3, G1, G2, G3, H1	B2, B3, C3, D8, D9, E2, E3, G2, G3, H1														
	#6 AWG Insulated Wire	.290 in.	A2, A3, B1, D4	A3, B2, D5	B2, D5, D6	B2, D5	A3, B2, D5	D4, D5, D6, H3	B2, D5, D6, H3														
EXPLANATION OF FASTENER CODES		A. <u>Staple Machine, Round Crown, Interior Use Only – (Note 6)</u>		D. <u>Clamp, One Hole Offset, Galvanized or Enameled, Interior and Exterior Use – (Note 7)</u>			F. <u>Nail, Station Wiring, Galvanized or Enameled, Interior and Exterior Use – (Note 7)</u>																
		1. 3/16" or 1/4" Crown – 3/8" Leg		<table><tr><th colspan="2">Wire Size</th><th rowspan="2">Fasteners (1), (2)</th></tr><tr><th>Min</th><th>Max</th></tr><tr><td colspan="2">1. 5/32" to 7/32"</td><td>1/2" x #6 RH Screw</td></tr><tr><td colspan="2">2. 5/32" to 7/32"</td><td>3/4" x #6 RH Screw</td></tr><tr><td colspan="2">3. 5/32" to 7/32"</td><td>1/8" x 3" Toggle Bolt</td></tr></table>			Wire Size		Fasteners (1), (2)	Min	Max	1. 5/32" to 7/32"		1/2" x #6 RH Screw	2. 5/32" to 7/32"		3/4" x #6 RH Screw	3. 5/32" to 7/32"		1/8" x 3" Toggle Bolt	1. Type B – 1/2"		
		Wire Size		Fasteners (1), (2)																			
		Min	Max																				
		1. 5/32" to 7/32"		1/2" x #6 RH Screw																			
		2. 5/32" to 7/32"		3/4" x #6 RH Screw																			
		3. 5/32" to 7/32"		1/8" x 3" Toggle Bolt																			
		2. 3/16" or 1/4" Crown – 7/16" or 9/16" Leg		2. 5/32" to 7/32"			2 Type B – 7/8"																
		3. 3/16" or 1/4" Crown – 9/16" Leg		3. 5/32" to 7/32"																			
		B. <u>Nail, Ground Wire, Single Shank Galvanized, Interior and Exterior Use</u>		4. 1/4" to 5/16"			1/2" x #6 RH Screw			G. <u>Clamp, One Hole Double – (Note 8)</u>													
5. 1/4" to 5/16"				1" x #6 RH Screw																			
6. 1/4" to 5/16"				1/8" x 3" Toggle Bolt																			
7. 1/8" to 5/32"				1/2" x #6 RH Screw																			
8. 1/8" to 5/32"				3/4" x #6 RH Screw																			
1. 7/8" #14		9. 1/8" to 5/32"			1/8" x 3" Toggle Bolt			3 Two 1/8" to 5/32"															
2. 1-3/8" #13								1/8" x 3" Toggle Bolt(2)															
C. <u>Clamp, Ground Wire, One Hole, Galvanized, Interior and Exterior Use</u>		E. <u>Clamp, Station Wiring, One Hole, Galvanized or Enameled, Interior and Exterior Use – (Note 7)</u>			H. <u>Station Wire Clip, Adhesive Backed, Interior Use Only –</u>																		
1. Type B-1/2" x #6 RH Screw (1)		1. Type B-1/2" x #6 RH Screw (1)			1. 1/8" Nominal																		
2. Type B-3/4" x #6 RH Screw (1)		2. Type B-3/4" x #6 RH Screw (1)			2. 3/16" Nominal																		
3. Type B-1/8" x 3" Toggle Bolt (2)		3. Type B-1/8" x 3" Toggle Bolt (2)			3. 1/4" Nominal																		

- Notes:**
- (1) Screw dimensions are minimum. Where appropriate, either or both dimensions shall be increased. All wood screws for exterior use shall be stainless steel. All other exterior metal devices shall be stainless steel, zinc coated steel, silicon bronze, or corrosion resistant aluminum alloy.
 - (2) Toggle bolt dimensions are minimum. Where appropriate, either or both dimensions shall be increased.
 - (3) Wall screw anchors may be used in wall board, plaster or tile walls. Screws and nails in masonry shall be secured by means of expansions type anchors. Equivalent manual or machine-driven devices may be used. Where toggle bolts are specified, equivalent devices may be used.
 - (4) Lead holes shall be drilled for screws, nails, and bridle rings in shingles and dropsiding.
 - (5) Sheet metal screws shall be used except where toggle bolts are required. Where wood sheathing under sheet metal siding is encountered, the sheet metal may be drilled or punched and a wood screw used.
 - (6) Machine-driven staples of nickel-copper composition may be used for exterior wiring.
 - (7) Galvanized clamps and wiring nails may be used for exterior and interior wiring. Enameled clamps shall be used for interior wiring only. Where toggle bolts or equivalent devices require holes in the structure larger than the clamp being fastened, a suitable washer of sufficient size to cover the hole must be used under the clamp.
 - (8) Double clamp may be used where two #22 AWG station wires, two #12 AWG grounding conductors, or one #22 AWG station wire and one #12 grounding conductor parallels one another.
 - (9) For converting English units to Metric units use 1 in. = 25.4 mm.

7.26 Grounding conductors shall be separated from "non-telecommunications company" wires in accordance with Section 800-12(b) of the ANSI/NFPA 70-1999, *NEC*®.

7.27 Grounding conductors run through metal conduits shall be bonded to the conduit at each end. RUS accepted and RUS technically accepted pipe type ground clamps and grounding connectors shall be used for bonding.

7.28 Where NID, BET, or fused station protector assembly units require grounding conductor connections to pipe systems, the following apply:

7.28.1 The connection shall be made to a cold water pipe of an operating water system;

7.28.2 The connection point shall be preferably inside the building;

7.28.3 Allow a minimum of 6 in. (152 mm) between the last fastener and the point where the grounding conductor first touches the water pipe;

7.28.4 Leave 2 in. (50.8 mm) of slack in the grounding conductor to avoid breaking the conductor at the terminating point. Tape the grounding conductor to the pipe where possible to avoid movement. In no case, shall the grounding conductor be coiled or wrapped around the pipe;

7.28.5 The pipe shall be cleaned with fine sand paper to make a good electrical connection. Care should be taken to avoid damaging the pipe while cleaning it;

7.28.6 Attach the pipe grounding conductor connector to the cleaned area of pipe and tighten. Care shall be exercised to avoid deforming, crushing, or otherwise damaging the pipe. A simple continuity check with an ohmmeter between the connector and the pipe will indicate whether or not a good electrical contact has been made. Set the ohmmeter to "Rx1" scale to ensure that a low resistance contact is made;

7.28.7 A warning tag shall be attached to the ground clamp with the following or equivalent statement: "Call the telecommunications company if this connector or grounding conductor is loose or must be removed;" and

7.28.8 When the water pipe is used, the ANSI/NFPA 70-1999, *NEC®*, requires that metal piping be used as a bonding conductor in this manner only when the connections to the pipe are within 5 ft (1.5 m) of where the pipe enters the premises.

7.29 Bonding conductors shall consist of either copper or tinned copper insulated wires of appropriate sizes.

7.29.1 Bonding conductors shall be run and attached in the same manner as grounding conductors.

7.29.2 Attaching and terminating devices for bonding conductors shall be adequate for the size of wire involved. The No. 6 AWG copper insulated conductor or larger shall not be terminated by bending it around a threaded stud.

7.30 Where NID, BET, or fused station protector assembly units require a driven ground rod the following shall apply to the ground rod installation:

7.30.1 Locate the ground rod at least 1 ft (300 mm) from buildings, poles, trees and other obstruction;

7.30.2 Ground rods shall not be installed within 6 ft (2 m) of electric service ground rods (Note: This minimum separation is provided to avoid mutual impedance effects of multiple grounding electrodes that will deleteriously degrade the effective impedance-to-earth if grounding electrodes are installed any closer than 6 ft (2 m) to one another. This requirement is included for cases where the telecommunications company is not allowed, for some reason, to observe the RUS preferred grounding method of attaching the primary protector grounding conductor directly to an accessible point on the building electric service grounding system. RUS believes that if the primary protector location can be sited within 6 ft (2 m) of the electric service ground rod then the electric service ground rod could be used as the preferred telecommunications grounding electrode and a separate telecommunications ground rod is unnecessary);

7.30.3 A hole, 15 in. (350 mm) deep and 6 in. (150 mm) in diameter, shall be dug at the location where the ground rod is to be driven;

7.30.4 Where "slip-on" type ground rod clamps are used instead of "clamp-around" type clamps, the ground rod clamps shall be placed onto the rod prior to driving the rod into the ground (Note there should be one clamp for the NID, BET, or fused station protector grounding conductor and one clamp for the conductor required to bond the telecommunications ground rod to the electric grounding system). However, the clamp shall not be tightened until the rod is completely driven. The end of the rod shall be placed in the bottom of the hole and the rod shall be aligned vertically adjacent to one wall of the hole prior to driving. The rod shall be driven until its tip is 12 in. (300 mm) below final grade. The grounding conductor shall then be attached, the clamp shall be tightened, and hole backfilled. Clamps employed in this manner shall be suitable for direct burial and shall be RUS accepted or RUS technically accepted; and

7.30.5 Where rods are manually driven, a large number of blows from a light hammer (4 lbs [1.8 kg]) shall be used instead of heavy sledgehammer type blows. This should keep the rod from bending.

7.31 Terminations on fuseless primary station protectors incorporated in NIDs and on fused primary station protectors shall be as shown in Figures 10, 11, 12, 13, 14, and 15 of this standard. The inner jackets of buried service wires and outer jackets of cables used as service drops shall be extended into the NID or the fused primary station protector. A 10 in. (250 mm) length of each spare wire shall be left in NIDs or fused primary station protectors. The spare wires shall be coiled up neatly and stored in the NID or fused primary station protector housing.

7.31.1 The shields of buried service wires may be connected to the ground binding post using RUS accepted or RUS technically accepted buried service shield bond connectors as shown in Figure 10 of this standard for NIDs and Figure 11 of this standard for fused primary station protectors. RUS accepted or RUS technically accepted buried service wire harness wires designed for customer access location installations may also be used for terminating buried service wire shields to the ground binding post of the NID as shown in Figure 12 and Figure 13 of this standard for fused primary station protectors.

7.31.2 On buried service drops and aerial service drops of more than 6 pairs using RUS accepted or RUS technically accepted cables, the shields shall be terminated with a RUS accepted or RUS technically accepted cable shield bonding connector and extended to the ground binding post of the NID, BET, or fused primary station protector with an RUS accepted or RUS technically accepted bonding harness wire. The installation of the shield bond connector and bonding harness wire shall be in accordance with the manufacturer's instructions.

7.31.3 The shield and other conductors at the fuseless primary station protector incorporated in the NID shall be terminated as shown on Figure 14 of this standard. The pronged or cupped washer shall be placed above the shield. The grounding conductor shall be placed around the post on top of the pronged or cupped washer. A flat washer shall be placed above the grounding conductor.

7.31.4 The station wire signaling ground conductor, if required, shall be placed above the first flat washer and beneath the second flat washer as indicated in Figure 14 of this standard.

7.31.5 The shield and other conductors at the fused primary station protector shall be terminated as shown on Figure 15 of this standard. The pronged or cupped washer shall be placed above the shield. The grounding conductor shall be placed around the post on top of the pronged or cupped washer. A flat washer shall be placed above the grounding conductor.

7.31.6 The station wire signaling ground conductor, if required, shall be placed above the first flat washer and beneath the second flat washer as indicated in Figure 15 of this standard.

7.31.7 Indoor NIDs or BETs that are equipped with "Quick Connect" type terminals shall not have more than one wire connected per clip. No. 19 AWG copper and No. 18 AWG copper covered-steel reinforced aerial service wire conductors shall not be connected to quick connect terminals. Nonmetallic reinforced aerial service wire using No. 22 AWG copper conductors may be connected to the quick connect terminals.

7.31.8 Tip and ring connections and other connections in multipair NIDs or BETs shall be as indicated in Figure 16 of this standard.

7.32 System polarity and conductor identification shall be maintained in NIDs, BETs, or fused primary station protectors in accordance with Construction Drawings 815 and 815-1 contained in Section 9 of this standard.

8. MOBILE HOMES

8.1 Customer access location installations at mobile homes shall be treated the same whether the homes are mounted on permanent foundations or temporary foundations and shall be installed as specified in Sections 1 through 9 of this standard. For the purpose of this standard, mobile homes include manufactured homes, motor homes, truck campers, travel trailers, and all forms of recreational vehicles. Customer access location installations at mobile homes can be considerably different than customer access location installations at regular homes and borrowers shall be certain that the two types of installations are properly applied.

8.2 The method of customer access location installation prescribed by the ANSI/NFPA 70-1999, *NEC®* for a mobile home depends on how the electric power is installed at the mobile home and it can involve considerable judgment on the part of the telecommunications installer. The *National Electrical Code®* and *NEC®* are registered trademarks of the National Fire Protection Association, Inc., Quincy, MA 02269. The ANSI/NFPA 70-1999, *NEC®*, requires primary station protectors to be located where specific acceptable grounding electrodes exist. The ANSI/NFPA 70-1999, *NEC®*, allows station protector installations to be at the location of the power meter or the electric disconnecting means apparatus serving the mobile home providing these electric facilities are installed in the manner specifically defined by the ANSI/NFPA 70-1999, *NEC®*. The ANSI/NFPA 70-1999, *NEC®*, requires the station protectors to be installed at the nearest of a number of other meticulously defined ANSI/NFPA 70-1999, *NEC®*, acceptable electrodes where the protector cannot be installed at the power meter or the electric disconnecting means apparatus serving the mobile home. The provisions can be confusing.

8.3 NIDs shall be installed at mobile homes as follows:

8.3.1 Where the mobile home electric service equipment (power meter, etc.,) or the electric service disconnecting means associated with the mobile home is located within 35 ft (10.7 m) of the exterior wall of the mobile home it serves, the NID shall be installed in accordance with Figure 17 of this standard; or

8.3.2 Where the mobile home electric service equipment (power meter, etc.,) or the electric service disconnecting means associated with the mobile home is located more than 35 ft (10.7 m) of the exterior wall of the mobile home it serves, the NID shall be installed in accordance with Figure 18 of this standard.

8.4 The service wire and station wire shall be terminated in the NID in accordance with Figure 19 of this standard.

8.5 Installation of the station wire and grounding conductor at the mobile home shall be in accordance with Figure 20 of this standard.


9. CONSTRUCTION AND ASSEMBLY UNIT DRAWINGS


9.1 The construction and assembly unit drawings in this standard shall be used by borrowers to assist the installer in making the customer access location installations.

9.2 The asterisk(s) appearing on the construction drawings indicate that the items are no longer listed in the RUS Informational Publication (IP) 344-2, "List of Materials Acceptable for Use on Telecommunications Systems of RUS Borrowers."

9.3 Drawings BM50, BM83, 312-1, 501-1, 501-2, 503-2, 504, 505, 506, 507, 508-1, 510, 510-1, 510-2, 513, 815, 815-1, 958, and 962 are as follows.


Page 46



Notes:

- ①. Where an obstruction of less than 2 in. is encountered, the buried service guard (item am) shall extend from the NID, BET, or fused protector to 6 in. below the ground.
- ②. Where an obstruction of greater than 2 in. is encountered, the buried service guard (item am) shall be divided as shown (from the NID, BET, or fused protector to the obstruction, and from 3 in. below the obstruction to 6 in. below the ground). In lieu of divided service guards (item am), a continuous flexible conduit may be used from the NID, BET, or fused protector to 6 in. below the ground.
- ③. For converting English units to metric units use 1 in. = 25.4 mm and 1 ft = 0.3048 m.

ITEM	MATERIAL	NO. REQ'D
am	Guard, buried service (including fasteners)	1
RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES BURIED SERVICE GUARD		
Scale: NTS		March 2001
		BM83



Notes:


- ① Where aerial service wire connections are made along aerial plastic cable, unprotected filled terminal blocks equipped with lead-out wires shall be used.
- ② Conductors of the aerial service wire shall be connected directly to the binding posts of the filled terminal block.

RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES
AERIAL PLASTIC CABLE DETAILS OF WIRE
CONNECTIONS TO FILLED TERMINAL BLOCKS

Scale: NTS

March 2001

312-1




— Preferably not more than 20 in. (508 mm) from cable suspension bolt.


— May be increased to 3 ft (0.9 m) to provide climbing space or clearances from trees.

— When greater than 3 ft (0.9 m) refer to drawing 501-2.

ITEMS	MATERIALS	NO. REQUIRED
*mm	Rings, drive	as required
*ns	Clamps, span	as required
mk	Clamps, drop wire	as required
nt	Wire, aerial service	as required
RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES SPAN CLAMP ATTACHMENT		
Scale: NTS		March 2001
		501-1



ITEMS	MATERIALS	NO. REQUIRED	
*mg	Hooks, drive	as required	
*ns	Clamps, span	as required	
mk	Clamps, drop wire	as required	
nt	Wire, aerial service	as required	
		RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES	
		SPAN CLAMP ATTACHMENT	
		Scale: NTS	March 2001
			501-2

Note:

- ①. Install aerial service wiring through all rings on bottom of terminal housing. Turn wire back around last ring to assigned pair. Form wire loosely to avoid sharp bends.

ITEMS	MATERIALS	NO. REQUIRED
*mg	Hooks, drive	as required
*ne	Rings, bridle	as required
er	Enclosures, ready-access	—
sh	Blocks, filled, terminal, unprotected	—
nt	Wire, aerial service	as required
mk	Clamps, drop wire	as required
RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES SERVICE WIRE CONNECTIONS TO AERIAL CABLE		
Scale: NTS		March 2001
		503-2




FIGURE A: Aerial service wires whose contact angle (A) exceeds five degrees and/or whose adjacent span lengths are different by 25 percent or more.





FIGURE B: Aerial service wires whose contact angle (A) is less than five degrees and/or whose adjacent span lengths are different by less than 25 percent.

ITEMS	MATERIALS	NO. REQUIRED
*mg	Hooks, drive	as required
nt	Wire, aerial service	as required
mk	Clamps, drop wire	as required
*mi	Support, drop wire	as required
RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES SERVICE WIRE ATTACHMENT AT INTERMEDIATE POLE		
Scale: NTS		March 2001
		504




MINIMUM STRINGING SAG – COPPER COVERED STEEL REINFORCED (CCSR) and
NONMETALLIC REINFORCED (NMR) AERIAL SERVICE WIRES

SPAN LENGTH ft (m)	SAG—MEDIUM AND LIGHT LOADING DISTRICTS	SAG—HEAVY LOADING DISTRICT
100 (30.5) OR LESS	20 in. (510 mm)	20 in. (510 mm)
125 (38)	34 in. (860 mm)	34 in. (860 mm)
150 (46)	4 ft (1.2 m)	4 ft (1.2 m)
175 (53)	5,5 ft (1.7 m)	7 ft (2.1 m)
200 (61)	7 ft (2.1 m)	11 ft (3.4 m)
225 (66.5)	9 ft (2.7 m)	
250 (76)	11 ft (3.4 m)	

Note: To reduce vibration and dancing, service wire shall be twisted one complete turn for each 10 ft (3 m) of span length at the time installation.

	RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES AERIAL SERVICE WIRE SAGS		
	Scale: NTS		March 2001
			505




Frame Buildings Where NIDs Containing Fuseless Station Protectors are Used on Fire Resistant Buildings.

Use house hook or drop wire hook for any angle except angle B. When necessary to place service wire within angle B use "S" knob with corner bracket to avoid service wire attachment on front of building.


Frame Buildings Where Fused Station Protectors are Used.

If angle A is less than 30° use "S" knob. If angle A is greater than 30° use "S" knob with 5/16 in. (7.9 mm) angle screw. When necessary to place service wire within angle B use "S" knob with corner bracket to avoid service wire attachments on front of buildings.



RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES			
SELECTION OF SERVICE WIRE ATTACHMENT			
Scale:	NTS		March 2001
			506



VERTICAL BUILDING RUN(Angle Screw)




VERTICAL BUILDING RUN

HORIZONTAL
BUILDING RUN
(Angle Screw)


HORIZONTAL BUILDING RUN

Notes:


- ①. Provide slack wire in the form of a smooth curve. Make sure exposed wire will not contact building.
- ②. Close drop wire clip firmly on wire with side cutting or equivalent pliers.
- ③. Bail of clamp shall not bear against aerial service wire.
- ④. All house attachments illustrated shall be firmly anchored in studs.
- ⑤. For converting English units to metric units use 1 in. = 25.4 mm.

HORIZONTAL BUILDING RUN
(Corner Bracket)





ITEMS	MATERIALS	ITEMS	MATERIALS
		—	Washer, 1.25 in. OD, 0.5 in. ID
mk	Clamp, drop wire	*mo	Screw, angle, 5/16 in.
*md	Bracket, house	nt	Wire, aerial service
*mr	Knob, insulator, "S"	*mj	Clip, drop wire
RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES INSULATED FIRST ATTACHMENTS FOR AERIAL SERVICE WIRE			
Scale: NTS		March 2001	
		507	



MASONRY






MASONRY OR FULL BRICK VENEER




Notes:

- ① See Table 4 for appropriate fasteners to be used with attachments. Expansion anchors not required on frame buildings, attachments must be firmly secured in studs.
- ② Provide slack wire in the form of a smooth curve.
- ③ For converting English units to metric units use 1 in. = 25.4 mm.



ITEMS	MATERIALS	ITEMS	MATERIALS
mk	Clamp, drop wire	*mw	Screw, R.H., stainless steel, wood
*md	Bracket, house	*my	Hook, drop wire
*mr	Knob, insulator, "S"	*ph	Anchor, expansion
—	Hook, house	np	Clamp, cable
		*mj	Clip, drop wire
		RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES	
		UNINSULATED FIRST ATTACHMENTS FOR	
		AERIAL SERVICE WIRE	
		Scale: NTS	March 2001
			508-1

INSIDE CORNERTURNNotes:



- ① Refer to Table 4 for appropriate fastening device.
- ② For converting English units to metric units use 1 in. = 25.4 mm.

OUTSIDE CORNER



ITEMS	MATERIALS	NO. REQUIRED
*pg	Screw eye, insulated	as required
*mr	Knob, insulator, "C"	as required
*mw	Screw, R.H., wood	as required
RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES INSULATED INTERMEDIATE ATTACHMENTS FOR SERVICE WRES		
Scale: NTS		March 2001
		510



TURNS




CORNERS




Note: For converting English units to metric units use 1 in. = 25.4 mm.

CORNERS

ITEMS	MATERIALS	NO. REQUIRED
*ne	Rings, bridle	as required
*mm	Rings, drive	as required
*np	Clamps, one-hole, offset	as required
RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES UNINSULATED INTERMEDIATE ATTACHMENTS FOR SERVICE WRES		
Scale: NTS		March 2001
		510-1




SKETCH A: Buried Service Above Grade Entrance



SKETCH B: Aerial Service Wire - Aerial Service Entrance


Notes:

- ① The first attachment of the buried wire to the building should be located approximately 4 inches above the ground. The remaining attachments shall be spaced approximately 14 inches apart.
- ② A porcelain or plastic tube shall be employed only when insulated attachments are required for support of aerial service wire on buildings.
- ③ Entrance hole shall be drilled to slope slightly upward. Except where a porcelain or plastic tube is required, all wires entering the hole shall be taped for a tight fit. When the aerial service wire approaches from above the entrance hole, a drip loop shall be made as shown.
- ④ Insert short piece of aerial service wire to cushion "C" knob.
- ⑤ Seal both ends of hole or conduit with duct seal.
- ⑥ For converting English units to metric units use 1 in. = 25.4 mm.




SKETCH C: Buried Service - Below Grade Entrance

ITEMS	MATERIALS	ITEMS	MATERIALS
*mr	Knob, insulator, "C"	*mw	Screw, wood
nt	Wire, aerial service	sa/sc	Wire or cable, filled, buried
-	Tube, plastic	sp	Sealer, duct
*np	Clamp, one-hole, offset		
RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES SERVICE ENTRANCES			
Scale: NTS		March 2001	
		510-2	




ITEMS	MATERIALS	ITEMS	MATERIALS
mk	Clamp, drop wire	nt	Wire, aerial service
*md	Bracket, corner	*pg	Screweyes, porcelain, insulated
*mr	Knob, "C"	*mr	Knob, insulator
		RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES AERIAL SERVICE WIRE RUN ON BUILDINGS	
		Scale: NTS	March 2001
			513

Conductor Polarity Diagram For NID Incorporating Fuseless Station Protector



Conductor Polarity Diagram For Fused Station Protector



Notes:


1. Refer to appropriate cable specifications for tip and ring conductor identification.
2. When facing the cable terminal the positive (tip) is on the left and the negative (ring) is on the right side of the pair.
3. Connections to be made in accordance with the manufacturer's instructions

RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES
CONDUCTOR POLARITY (TIP AND RING) DIAGRAM
(AERIAL PLANT)

Scale: NTS

March 2001


815



Notes:

- 1. Refer to appropriate cable specifications for tip and ring conductor identification.
- 2. Connections to be made in accordance with the manufacturer's instructions.
- 3. Connections to be made in accordance with RUS Bulletin 1753F-401(PC-2), "RUS Standard for Splicing Copper and Fiber Optic Cables."

	RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES BURIED PLANT CONDUCTOR POLARITY DIAGRAM		
	Scale: NTS		March 2001
			815-1




Notes:


- ①. Markers shall be installed on all buried wires and cables at each housing as shown in RUS Bulletin 1753F-401.
- ②. The marker shall be wrapped around the cable in a manner such that the printed portion of the marker is completely covered and protected by at least one layer of transparent tape. On cables too large for this to be accomplished with a single marker, a second marker shall be applied so that the clear tape of the second marker provides protection for the printed portion of the first. The information shall be legibly printed and shall be readily visible.
- ③. The markers shall contain the following information unless indicated otherwise by the Borrower or Borrower's Engineer.
 Buried Service Wire:
 Line 1 – Subscribers identification (Such as: name, telephone number, or address)

 Buried Cable or Wire:
 Line 1 – Nearest sequential marking
 Line 2 – Direction of cable or wire
 Line 3 – Cable reel number
 Line 4 – Name of cable manufacturer
- ④. Other methods or materials of directional marking may be used when specified by the Borrower or the Borrower's Engineer.


Buried Service Wire Marker



Buried Cable Marker



ITEM	MATERIAL	NO. REQ'D
*tm	Tape, marker	as required
RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES BURIED CABLE AND WIRE DIRECTIONAL MARKING		
Scale: NTS		March 2001
		958




Notes:

- ①. When mounting NID, BET, or fused station protector and clamps on masonry surface, use screw expansion anchors or equivalent manual or machine-driven devices.
- ②. Attach filled buried service wire or cable to building with one-hole offset clamps spaced 14 in. max. apart. Where grounding conductor parallels service wire or cable, both wires may be run under the same attachment.
- ③. Place filled buried service wire or cable snug against building.
- ④. Details of NID, BET, or Fused station protector terminations are shown on Figures 10 through 16 and Figure 19 of this standard.
- ⑤. For converting English units to metric units use 1 in = 25.4 mm and 1 ft = 0.3048 m.


ITEMS	MATERIALS	ITEMS	MATERIALS
NID	NID, protected, station, outside	*rg	Wire, station
sa	Wire, filled, buried	*mw	Screw, stainless steel, wood
*ph	Anchor, expansion, screw	sc	Cable, filled, buried
*np	Clamp, one-hole, offset		
		RURAL TELECOMMUNICATIONS CONSTRUCTION PRACTICES BURIED WIRE SERVICE INSTALLATION ON BUILDINGS	
		Scale: NTS	March 2001
			962

FIGURE 1 ANCHORING DEVICES

HAMMER DRIVE ANCHORS



SCREW ANCHOR



MACHINE BOLT ANCHOR




FIGURE 2 CABLE ATTACHMENT DEVICES






FIGURE 3


CABLE ENTRANCES AND RUNS IN BUILDINGS



SKETCH A



SKETCH B




SKETCH C

Notes:


- (1) Recommended maximum is shown; length cannot exceed the ANSI/NFPA 70-1999, NEC[®] allowable length of 50 ft (15.2 m). (See Fine Print Note No. 2 of Section 800-50 of ANSI/NFPA 70-1999, NEC[®])
- (2) Outside plant cable shield shall be connected to an acceptable grounding electrode. If splice case is metallic, the splice case shall also be connected to the same acceptable grounding electrode.

FIGURE 4


AERIAL SERVICE WIRE CROSSING OBSTRUCTIONS WOODEN BUILDING SURFACES




SKETCH A: PASSING BEHIND DRAIN SPOUT
(PREFERRED INSTALLATION METHOD)




SKETCH B: PASSING IN FRONT OF DRAIN SPOUT



SKETCH C: CROSSING IN FRONT OF CONDUIT





SKETCH D: CROSSING BEHIND CONDUIT
(PREFERRED INSTALLATION METHOD)




SKETCH E: PASSING POWER, RADIO, OR GROUNDING CONDUCTOR




FIGURE 5

AERIAL SERVICE WIRE CROSSING OBSTRUCTIONS
MASONRY BUILDING SURFACESSKETCH A: PASSING BEHIND DRAIN SPOUT
(PREFERRED INSTALLATION METHOD)

SKETCH B: PASSING IN FRONT OF DRAIN SPOUT



SKETCH C: CROSSING IN FRONT OF CONDUIT

SKETCH D: CROSSING BEHIND CONDUIT
(PREFERRED INSTALLATION METHOD)SKETCH E: PASSING BEHIND FOREIGN WIRE
(PREFERRED INSTALLATION METHOD)

SKETCH F: MASONRY BUILDING PROJECTIONS

FIGURE 6
AERIAL SERVICE WIRE CROSSING COMBUSTIBLE BUILDING PROJECTIONS







FIGURE 7
SUSPENSION STRAND DEADENDING ON BUILDINGS



SKETCH A: PULL ALONG LINE OF BUILDING WALL



SKETCH B: ANGLE PULL FROM BUILDING WALL


SKETCH C: PULL FROM FACE OF WALL

GROUNDING OF TELECOMMUNICATIONS SERVICE TO ELECTRIC SERVICE (PREFERRED METHOD)



1. See Section 800-40(a) of ANSI/NFPA 70-1999 NEC[®].
2. Select one of the attachment options shown above for the installation.
3. Clamp must be accepted by Listing Agency (UL, etc.).
4. Connector (Item "me") must be accepted by a Nationally recognized testing laboratory.

FIGURE 9



ALTERNATIVE TECHNIQUE FOR BONDING TO ELECTRIC SERVICE GROUND
WHERE DIRECT ATTACHMENT IS NOT POSSIBLENotes:

- ① Both electric and telephone "aj" connectors attached to the cold water pipe shall be within 5 ft (1.5 m) of where the pipe enters the premises.
- ② Refer to Paragraph 7.22, Table 5, of this standard for the ground wire conductor size. Ground wire must be accepted by a Nationally recognized testing laboratory.
- ③ Connector "aj" must be accepted by a Nationally recognized testing laboratory.

FIGURE 10

BONDING BURIED SERVICE WIRE AT STATION PROTECTOR OF NID
USING SERVICE WIRE SHIELD BOND CONNECTOR

Installed Buried
Service Wire



Typical Preparation of
Buried Service Wire

FIGURE 11
BONDING BURIED SERVICE WIRE AT FUSED STATION PROTECTOR
USING SERVICE WIRE SHIELD BOND CONNECTOR




FIGURE 12

BONDING BURIED SERVICE WIRE AT STATION PROTECTOR OF NID USING SERVICE WIRE BONDING HARNESS




FIGURE 13

BONDING BURIED SERVICE WIRE AT FUSED STATION PROTECTOR USING SERVICE WIRE BONDING HARNESS





FIGURE 14


TERMINATION OF CONDUCTORS AND SHIELD ON STATION PROTECTOR BINDING POSTS OF NID



Notes:

1. If shoulder is inadequate to support shield or wire add a flat washer.
2. Terminate buried service wire shield with station protector grounding lug of NID in accordance with either Figure 10 or 12 of this standard.


FIGURE 15

TERMINATION OF CONDUCTORS AND SHIELD ON
FUSED STATION PROTECTOR BINDING POSTSNotes:

- (1) If shoulder is inadequate to support shield or wire add a flat washer.
- (2) Terminate buried service wire shield on fused station protector grounding lug in accordance with either Figure 11 or 13 of this standard.

FIGURE 16


MULTIPAIR NID OR BET TERMINAL CONNECTIONS CONTAINING FUSELESS STATION PROTECTORS



Note: #18 AWG copper-covered steel reinforced aerial service conductors shall not be connected to quick connect terminals. Nonmetallic reinforced aerial service conductors (#22 AWG copper) may be connected to quick connect terminals.

FIGURE 17


NETWORK INTERFACE DEVICE (NID) INSTALLATION ELECTRIC SERVICE EQUIPMENT WITHIN 35 FEET (10.7 METERS) OF MOBILE HOME



- Notes:
- ① Clamp must be accepted by Listing Agency (UL, etc.) for two conductors, otherwise two clamps must be used.
 - ② See Figure 19 of this standard for NID terminations.
 - ③ See Figure 20 of this standard for mobile home installation.
 - ④ Bare if buried its entire length; insulated where human contact is possible.
 - ⑤ Refer to Paragraph 7.22, Table 5, of this standard for the correct conductor size of the ground wire.

FIGURE 18

NETWORK INTERFACE DEVICE (NID) INSTALLATION ELECTRIC SERVICE EQUIPMENT MORE THAN 35 FEET (10.7 METERS) FROM MOBILE HOME



Notes: (1) Clamp must be accepted by Listing Agency (UL, etc.) for two conductors, otherwise two clamps must be used. (2) See Figure 19 of this standard for NID terminations. (3) See Figure 20 of this standard for mobile home installation. (4) Refer to Paragraph 7.22, Table 5, of this standard for the correct conductor size of the ground wire.

FIGURE 19
NID TERMINATIONS




FIGURE 20
MOBILE HOME INSTALLATION

